


Shivshahi Punarvasan Prakalp Ltd.

5th Floor, Griha Nirman Bhavan, Bandra (E), Mumbai- 400 051.

QUOTATION NOTICE

1. Quotations in sealed covers are invited from the Contractors so as to reach the office of the undersigned at Shivshahi Punarvasan Prakalp Ltd. Griha Nirman Bhavan, Bandra (E), Mumbai- 400 051 **on or before 25/09/2020 upto 3.00 p.m. for the work of Providing and fixing new partition, P/F table, P/F marine ply wood for partition, P/F PVC flooring in Minister's cabin at SPPL office.**
2. **The estimated cost of the work is Rs. 2,49,239.00** (Rupees Two lakhs Forty Nine Thousand Two Hundred Thirty Nine only).
3. The quotations in sealed cover shall be addressed to the Executive Engineer, Shivshahi Punarvasan Prakalp Ltd., Griha Nirman Bhavan, Bandra (East), Mumbai- 400 051. The blank quotations can be downloaded from the tender section of SPPL website www.sppl.biz from **18/09/2020 to 25/09/2020 upto 2.00 p.m.**
4. The quotationer shall quote in ink his percentage offer above/below or at par the estimated cost both in figures and words. The quotation should be submitted in a single sealed Envelope containing forwarding letter, quotation notice and duly filled Schedule-B and signed on each page.
5. The name of work for which quotations have been given should be stated clearly on the envelope containing the quotation and name of Contractor should be written on lower left of envelope.
6. The sealed quotation will be received by the office of Executive Engineer/SPPL, 5th floor, Griha Nirman Bhavan, Bandra (East), Mumbai – 400 051 upto **3.00 p.m.** by **25/09/2020** and will be opened at **3.30 p.m.** on the same day as far as possible in the presence of the contractors/their representatives whosoever remain present at that time.
7. The quantities as shown in Schedule 'B' are approximate. The payment will be made as per actual quantity of work done.
8. The acceptance of quotation shall rest with the competent authority who reserves the right to reject any or all the quotations without assigning any reason for doing so.
9. The quotation submitted by the quotationer shall be binding on him for a period of 90 days from the last date of receipt of quotation.
10. No alternation in the form of quotation or schedule of quantities, specifications shall be entertained.
11. The entire work is to be completed within **180 days**.
12. The work shall be carried out in accordance with I.S. specifications for the particular items and as per the detailed specifications mentioned in Schedule-B.
13. The rates quoted shall be inclusive of all taxes, Octroi Duty and free delivery at site of work and nothing extra shall be paid on any account.

14. The quotationer is advised to visit and examine the site of work and its surroundings before quoting the rate and acquaint themselves with the site conditions.
15. The contractor will have to make his/ their own arrangement at his/their cost for office and stores and safeguard the materials brought on the work and the materials issued by the department if any.
16. The contractor shall provide all labors, tools, pegs, watering and all other materials as required for line out and setting out the layout etc. for the work without claiming any payment.
17. After the completion of the work, the contractor shall remove forthwith all his/ their serviceable and un-serviceable materials from site of work and other debris shall be dumped and leveled as ordered within the scope of work if so ordered without any extra cost.
18. GST if applicable, will be paid separately.
19. No escalation shall be paid to the contractor.
20. The successful quotationer shall have to enter into A-1 Agreement with the Executive Engineer/SPPL as per the rules in force.


Executive Engineer,
Shivshahi Punarvasan Prakalp Ltd.
Mumbai- 400 051.

No. SPPL/ GM(Engg)/EE/ 502 /2020,
Office of the Executive Engineer
Shivshahi Punarvasan Prakalp Ltd.
Griha Nirman Bhavan, Bandra (E),
Mumbai- 400 051.

Date : 18 / 09 / 2020

Issued to :

M/s. _____

Copy submitted to G.M. (Finance)/SPPL for information.

Copy submitted to Dy.CE/SPPL for information.

Copy f.w.c's to Accounts Officer/SPPL for information.

Copy to D.E./SPPL for information & necessary action.

Copy to Notice Board/SPPL.

✓ Copy to M/s. IMPAQ TECHNOLOGIES PVT. LTD. for publishing quotation notice along with Schedule-B on SPPL website.

NAME OF WORK : Providing and fixing new partition, P/F table, P/F marine ply wood for partition, P/F PVC flooring in Minister's cabin at SPPL office.

: SCHEDULE 'B' :							
Item. No.	Std. Specification	Quantity	Description	Rate		Unit	Amount
				In Figure	In words		
1	As per wording of Item.	2.19	Providing and fixing C.t.wood frame partition of size 2"x1-1/2" for the partition at 60 cm x 60 cm horizontal & vertical as per design & drawing including all material, labour, transportation complete. With required fevicol, nails, G.I. screws etc. and as directed by Engineer in Charge. (Plywood & mica to be paid seperatly)(Excluding GST Taxes)	1399.68	Rupees One Thousand Three Hundred Ninety Nine point Sixty Eight only.	Sq.Mt.	3065.30
2	As per wording of Item.	4.74	Providing and fixing 6mm thick Marine plywood IS 710-303 ply for paneling / partition (without T.Wood frame) and finishing external face by 1.00 mm thick mica laminate sheet including fevicol, nails, screws etc. complete and as directed by Engineer-in-charge. (excluding frame work). (Excluding GST taxes)	2806.49	Rupees Two Thousand Eight Hundred Six point Forty Nine only.	Sq.Mt.	13302.76
3	As per wording of Item.	2.00	Providing and fixing Table having dimensions as 1.21 m (L)x 0.61 m (B)x 0.76 m (D) i.e. 4'-0" (L), 2'-0" (B), 2'-6" (D) having 18/19mm thick Marine plywood IS 710-303 ply for table top, table sides, top and side supports (15cm wide), drawer box sides, bottom, drawer front, foot rest, 12 mm thick Marine plywood IS 710-303 ply for drawer sides and back, table back, 6 mm thick Marine plywood IS 710-303 ply for drawer base, lapping patti wherever required, 1 mm thick laminate sheet of approved quality, colour and shade to all exposed faces, french polish to all unexposed faces, approved make 450 mm long telescopic channle for drawers, handle, lock for all drawer, including all the material mentioned above and fevicol, nails, screws, all taxes, transportion, loading, unloading, labour etc complete as directed by Engineer-in-charge. (Excluding all Taxes)	23318.00	RupeesTwenty Three Thousand Three Hundred Eighteen only.	No.	46636.00
4	As per wording of Item.	1.47	Providing and fixing 6mm thick clear glass on Table top of approved make like Modiguard/Sain Gobain etc. with pencil dhar polish from all four side including all labour, transport, loading/unloading upto Gr. floor etc. complete. (Excluding GST Taxes)	3294.25	Rupees Three Thousand Two Hundred Ninety Four point Twenty Five only.	Sq.Mt.	4842.55

Item No.	Std. Specification	Quantity	Description	Rate		Unit	Amount
				In Figure	In words		
5	As per wording of Item.	62.62	Providing & fixing PVC plank textured tile 36x6 for flooring 2.00 thick including, filling undulations white cement, with replacing broken tiles if any, pasting & levelling the surface, cleaning, moving & rearranging office furniture etc. complete. (Excluding all taxes)(Sample to be approved prior to Executive from concern Engineer in charge.)	1807.60	Rupees One Thousand Eight Hundred Seven point Sixty only.	Sq.Mt.	113191.91
6	As per wording of Item.	4.50	Providing & fixing low height storage unit 0.45 m deep and 0.76 m high having 18/19 mm Marine plywood IS-701/303 ply for top, sides, back, front part, base, horizontal and vertical partition with 1 mm thick laminate sheet of approved colour and quality fixed on all the exposed faces and french polishing to remaining portion including hinges, handle, lock, magnet catch including all the material mentioned above and fevicol, secrows, nails, transportation etc. complete as directed by Engineer-in-charge and consulting Architect. (Excluding GST)	15050.15	Rupees Fifteen Thousand Fifty point Fifteen only.	Rmt.	67725.68
7	(It.60(b), Pg.161, PWD DSR 2015-16)	5.00	Shooting of still photographs outdoor and indoor of construction and other works of building, bridges, roads, etc. in district and outside district at any distance. (Still Photo 4" x 6" size)	95.00	Rupees Ninety Five only.	03 Copies each photo	475.00
Total Rs.							2,49,239.20
Say Rs.							2,49,239.00

(Rupees Two Lakhs Forty Four Thousand One Hundred Thirty Six only)

I/We hereby agree to quote _____ % Above/Below or At par with the estimated cost put to the tender.

Therefore, the amount (in figure) _____ (in words) _____

Signature of Contractor/s


Executive Engineer / SPPL