


Shivshahi Punarvasan Prakalp Ltd.

5th Floor, Griha Nirman Bhavan, Bandra (E), Mumbai- 400 051.

QUOTATION NOTICE

1. Quotations in sealed covers are invited from the Contractors so as to reach the office of the undersigned at Shivshahi Punarvasan Prakalp Ltd. Griha Nirman Bhavan, Bandra (E), Mumbai- 400 051 **on or before 06/12/2018 upt 3.00 p.m. for the work of providing installing and testing of mono-block pump set in pump room, complete rewinding of motor & painting for surface mounted pump set, providing and fixing shutter to wall made from marine ply panel and miscellaneous electrical works in meter room electrical works in meter room at Building no. 1 (A3) under S.R. Scheme at Antop Hill, Wadala, Mumbai.**
2. **The estimated cost of the work is Rs. 2,86,034.00 (Rupees Two Lakhs Eighty Six Thousand Thirty Four only).**
3. The quotations in sealed cover shall be addressed to the Executive Engineer (City), Shivshahi Punarvasan Prakalp Ltd., Griha Nirman Bhavan, Bandra (East), Mumbai- 400 051. The blank quotations can be downloaded from the tender section of SPPL website www.sppl.biz from **29/11/2018 to 06/12/2018 upto 2.00 p.m.**
4. The quotationer shall quote in ink his percentage offer above/below or at par the estimated cost both in figures and words. The quotation should be submitted in a single sealed Envelope containing forwarding letter, quotation notice and duly filled Schedule-B and signed on each page.
5. The name of work for which quotations have been given should be stated clearly on the envelope containing the quotation and name of Contractor should be written on lower left of envelope.
6. The sealed quotation will be received by the office of Executive Engineer (City)/SPPL, 5th floor, Griha Nirman Bhavan, Bandra (East), Mumbai – 400 051 upto **3.00 p.m. by 06/12/2018** and will be opened at **3.30 p.m.** on the same day as far as possible in the presence of the contractors/their representatives whosoever remain present at that time.
7. The quantities as shown in Schedule 'B' are approximate. The payment will be made as per actual quantity of work done.
8. The acceptance of quotation shall rest with the competent authority who reserves the right to reject any or all the quotations without assigning any reason for doing so.
9. The quotation submitted by the quotationer shall be binding on him for a period of 30 days from the last date of receipt of quotation.
10. No alternation in the form of quotation or schedule of quantities, specifications shall be entertained.
11. The entire work is to be completed within **60 days.**
12. The work shall be carried out in accordance with I.S. specifications for the particular items and as per the detailed specifications mentioned in Schedule-B.

13. The rates quoted shall be inclusive of all taxes, Octroi Duty and free delivery at site of work and nothing extra shall be paid on any account.
14. The quotationer is advised to visit and examine the site of work and its surroundings before quoting the rate and acquaint themselves with the site conditions.
15. The contractor will have to make his/ their own arrangement at his/their cost for office and stores and safeguard the materials brought on the work and the materials issued by the department if any.
16. The contractor shall provide all labors, tools, pegs, watering and all other materials as required for line out and setting out the layout etc. for the work without claiming any payment.
17. After the completion of the work, the contractor shall remove forthwith all his/ their serviceable and un-serviceable materials from site of work and other debris shall be dumped and leveled as ordered within the scope of work if so ordered without any extra cost.
18. No escalation shall be paid to the contractor.
19. The successful quotationer shall have to enter into A-1 Agreement with the Executive Engineer (City)/SPPL as per the rules in force.


Executive Engineer (City),
Shivshahi Punarvasan Prakalp Ltd.
Mumbai- 400 051.

No. SPPL/ GM(Engg)/EE(City)/ **1443**/2018,
Office of the Executive Engineer
Shivshahi Punarvasan Prakalp Ltd.
Griha Nirman Bhavan, Bandra (E),
Mumbai- 400 051.

Date : 29 / 11 / 2018

Issued to :

M/s. _____

Copy submitted to G.M. (Finance)/SPPL for information.

Copy submitted to Dy.CE/SPPL for information.

Copy f.w.c's to Accounts Officer/SPPL for information.

Copy to D.E./SPPL for information & necessary action

Copy to Notice Board/SPPL.

✓ Copy to M/s. IMPAQ TECHNOLOGIES PVT. LTD. for publishing quotation notice along with Schedule-B on SPPL website.

NAME OF WORK : Providing installing and testing of mono-block pump set in pump room, complete rewinding of motor & painting for surface mounted pump set, providing and fixing shutter to wall made from marine ply panel and miscellaneous electrical works in meter room at Building no. 1 (A3) under S.R. Scheme at Antop Hill, Wadala, Mumbai.

: SCHEDULE 'B' :							
Item. No.	Std. Specification	Quantity	Description	Rate		Unit	Amount
				In Figure	In words		
1	It.97, Pg.112, PWD DSR 2015-16)	15.50	Providing and fixing shutter to wall cupboard made from 12mm thick Marine ply. Panel with of paint face and approved colour laminated face form outer side including lipping, beading, brass oxidised fixtures and fastenings etc. complete.	2563.00	Rupees Two thousand five hundred sixty three only.	Sq.Mt.	39726.50
2	ME-4-12-t of MCGM's Mains and Submains wiring, Point wiring SOR 2018	142.00	Supply and fixing of Step type Electronic Fan Regulator minimum rated for 100W	448.00	Rupees Four Hundred Forty Eight only.	Nos.	63616.00
3	It. No. 1-2-24, Page 14 (PWD Electrical DSR 2017-18)	146.00	Supplying & erecting UPVC gland/ adaptor suitable for 20 mm dia pvc pipe.	17.00	Rupees Seventeen only.	Each	2482.00
4	It. No. 7-9-1, Page 160 (PWD Electrical DSR 2017-18)	71.00	Supplying & erecting crimping type copper lugs for cable upto 16 sq mm complete as per specification No. CBCL/ CU	18.00	Rupees Eighteen only.	Each	1278.00
5	It. No. 9-2-2, Page 184 (PWD Electrical DSR 2017-18)	1.00	Supplying and erecting G.I. strip of required size used for earthing on wall and/or any other purpose with necessary GI clamps fixed on wall painted with insulating and non corrosive bond in an approved manner with joint required. as per specification No (EA-EP).	851.00	Rupees Eight Hundred Fifty One only.	Kg.	851.00
6	It. No. 1-2-7, Page 13 (PWD Electrical DSR 2017-18)	845.60	Supplying and erecting rigid PVC conduit 20 mm dia. with PVC accessories on wall / ceiling as per specification No: WG-MA/CON, para no. 1.1.1 (Labour Charges).	15.00	Rupees Fifteen only.	Meter	12684.00
7	It. No. 12-8-6, Page 266 (PWD Electrical DSR 2017-18)	2.00	Dismantling the existing submersible pump with GI pipeline upto 10m depth (For additional depth of each 3 m or part thereof add Rs. 50/- per 3m, in the rates)	2516.00	Rupees Two thousand five hundred sixteen only.	Each	5032.00

Item No.	Std. Specification	Quantity	Description	Rate		Unit	Amount
				In Figure	In words		
8	R2-ME-6-4-x, (MCGM's Mechanical & Electrical SOR 2018)	1.00	Monoblock Pumpsets (SP-ME-TS-14) Providing, installing and testing of monoblock pumpset equipped with all required accessories like priming cup, air vent, suction & delivery pressure gauge etc. 7.5 H.P. three phase motor, with head of (40-56 mtr.) giving discharge of (5.75 - 1.75 lps) (50 x 40mm). Pump body: Cast Iron, Impeller : Cast Iron, Shaft SS410.	53072.00	Rupees Fifty Three Thousand Seventy Two only.	Nos.	53072.00
9	R2-ME-6-8-g, (MCGM's Mechanical & Electrical SOR 2018)	2.00	SUPPLYING & FIXING VALVES: GUN METAL FOOT VALVE (SPRING LOADED): (SP-ME-TS-72) 65 mm dia.	3858.00	Rupees Three Thousand Eight Hundred Fifty Eight only.	No.	7716.00
10	It. No. 5-1-6, Page 97 (PWD Electrical DSR 2017-18)	3.00	Supplying and erecting Triple pole metal/ iron clad switch & fuse 415/ 500V 32A on iron frame/board as per specification C27No. SW-SWR/MTP.	1545.00	Rupees One Thousand Five Hundred Forty Five only.	Each	4635.00
11	It. No. 2-9-4, Page 61 (PWD Electrical DSR 2017-18)	6.00	Supplying and erecting LED street light fitting suitable for above 40W to 48W lamp, including lamp, with PF> 0.95 class IP 65 and above Housing of pressure die cast alluminum alloy and heat sink extruded alluminum complete per specification No. FG-ODF/FLS2	4439.00	Rupees Four Thousand Four Hundred Thirty Nine only.	Each	26634.00
12	R2-ME-8-22-e, (MCGM's Mechanical & Electrical SOR 2018)	1.00	COMPLETE REWINDING OF MOTOR & PAINTING FOR SURFACE MOUNTED PUMPSET. 7.5 H.P. induction motor.	11014.00	Rupees Eleven Thousand Fourteen only.	Nos.	11014.00
13	It. No. 12-5-2, Page 260 (PWD Electrical DSR 2017-18)	2.00	Supplying and erecting D.O.L. Starter 400V. 3 phase, 50 cycles with no volt coil and overload element with necessary materials and connected to supply upto 7.5 H.P. (Similar to L & T make MK-1 DOL Model)	2266.00	Rupees Two Thousand Two Hundred Sixty Six only.	Each	4532.00
14	It. No. 7-2-2, Page 147 (PWD Electrical DSR 2017-18)	45.00	Supplying & erecting PVC armoured cable 2 core 4 sq mm copper conductor continuous 5.48 sq mm (12 SWG) G.I. earth wire complete erected with glands & lugs, on wall/ trusses/pole or laid in provided trench/ pipe as per specification no. CB-LT/CU.	202.00	Rupees Two Hundred Two only.	Meter	9090.00

Item. No.	Std. Specification	Quantity	Description	Rate		Unit	Amount
				In Figure	In words		
15	R2-ME-1-17-d, (MCGM's Mechanical & Electrical SOR 2018)	77.00	Unit rate of 240V/415V, 'C' Curve, 10KA, Miniature circuit breaker suitable for DB mounting complete with connection, testing & commissioning etc. 32A SP MCB	335.00	Rupees Three Hundred Thirty Five only.	Nos.	25795.00
16	It. No. 5-6-15, Page 112 (PWD Electrical DSR 2017-18)	77.00	Supplying & fixing CRCA sheet Box with earthing terminals for housing 2 Pole RCCB/RCCB+MCB complete on iron frame/laminated board.	226.00	Rupees Two Hundred Twenty Six only.	Each	17402.00
17	(It.60(b), Pg.161, PWD DSR 2015-16)	5.00	Shooting of still photographs outdoor and indoor of construction and other works of building, bridges, roads, etc. in district and outside district at any distance. (Still Photo 4" x 6" size)	95.00	Rupees Ninety Five only.	03 Copies each photo	475.00
						Total Rs.	286,034.50
						Say Rs.	286,034.00

(Rupees Two Lakhs Eighty Six Thousand Thirty Four only)

I/We hereby agree to quote _____% Above/Below or At par with the estimated cost put to the tender.

Therefore, the amount (in figure) _____ (in words) _____

Signature of Contractor/s


 Executive Engineer (City)/SPPL