

Shivshahi Punarvasan Prakalp Ltd.

5th Floor, Griha Nirman Bhavan, Bandra (E), Mumbai- 400 051.

QUOTATION NOTICE

1. Quotations in sealed covers are invited from the Contractors so as to reach the office of the undersigned at Shivshahi Punarvasan Prakalp Ltd. Griha Nirman Bhavan, Bandra (E), Mumbai- 400 051 **on or before 03/09/2019 upt 3.00 p.m. for the work of Providing & fixing aluminum two track sliding window and providing & fixing M.S. safety grills and G.I. wire mesh to windows in Amenity building no. D6 under S.R. Scheme at Dindoshi, bearing CTS No. 827D/4, Dindoshi, CTS No. 827D/4, Dindoshi, Malad (East), Mumbai.**
2. The estimated cost of the work is **Rs. 2,96,057.00** (Rupees Two Lakhs Ninety Six Thousand Fifty Seven only).
3. The quotations in sealed cover shall be addressed to the Executive Engineer (Dharavi), Shivshahi Punarvasan Prakalp Ltd., Griha Nirman Bhavan, Bandra (East), Mumbai- 400 051. The blank quotations can be downloaded from the tender section of SPPL website www.sppl.biz from **26/08/2019** to **03/09/2019** upto **2.00 p.m.**
4. The quotationer shall quote in ink his percentage offer above/below or at par the estimated cost both in figures and words. The quotation should be submitted in a single sealed Envelope containing forwarding letter, quotation notice and duly filled Schedule-B and signed on each page.
5. The name of work for which quotations have been given should be stated clearly on the envelope containing the quotation and name of Contractor should be written on lower left of envelope.
6. The sealed quotation will be received by the office of Executive Engineer (Dharavi)/SPPL, 5th floor, Griha Nirman Bhavan, Bandra (East), Mumbai – 400 051 upto **3.00 p.m.** by **03/09/2019** and will be opened at **3.30 p.m.** on the same day as far as possible in the presence of the contractors/their representatives whosoever remain present at that time.
7. The quantities as shown in Schedule 'B' are approximate. The payment will be made as per actual quantity of work done.
8. The acceptance of quotation shall rest with the competent authority who reserves the right to reject any or all the quotations without assigning any reason for doing so.
9. The quotation submitted by the quotationer shall be binding on him for a period of 30 days from the last date of receipt of quotation.
10. No alternation in the form of quotation or schedule of quantities, specifications shall be entertained.
11. The entire work is to be completed within **60 days**.
12. The work shall be carried out in accordance with I.S. specifications for the particular items and as per the detailed specifications mentioned in Schedule-B.

13. The rates quoted shall be inclusive of all taxes, Octroi Duty and free delivery at site of work and nothing extra shall be paid on any account.
14. The quotationer is advised to visit and examine the site of work and its surroundings before quoting the rate and acquaint themselves with the site conditions.
15. The contractor will have to make his/ their own arrangement at his/their cost for office and stores and safeguard the materials brought on the work and the materials issued by the department if any.
16. The contractor shall provide all labors, tools, pegs, watering and all other materials as required for line out and setting out the layout etc. for the work without claiming any payment.
17. After the completion of the work, the contractor shall remove forthwith all his/ their serviceable and un-serviceable materials from site of work and other debris shall be dumped and leveled as ordered within the scope of work if so ordered without any extra cost.
18. No escalation shall be paid to the contractor.
19. The successful quotationer shall have to enter into A-1 Agreement with the Executive Engineer (Dharavi)/SPPL as per the rules in force.

Executive Engineer (Dharavi).
Shivshahi Punarvasan Prakalp Ltd.
Mumbai- 400 051.

No. SPPL/ GM(Engg)/EE(Dharavi)/ 1115 /2019.
Office of the Executive Engineer
Shivshahi Punarvasan Prakalp Ltd.
Griha Nirman Bhavan, Bandra (E),
Mumbai- 400 051.

Date : 26 / 08 / 2019

Issued to :

M/s. _____

Copy submitted to G.M. (Finance)/SPPL for information.

Copy submitted to Dy.CE/SPPL for information.

Copy f.w.c's to Accounts Officer/SPPL for information.

Copy to D.E./SPPL for information & necessary action

Copy to Notice Board/SPPL.

✓ Copy to M/s. IMPAQ TECHNOLOGIES PVT. LTD. for publishing quotation notice along with Schedule-B on SPPL website.

NAME OF WORK : Providing & fixing aluminum two track sliding window and providing & fixing M.S. safety grills and G.I. wire mesh to windows in Amenity building no. D6 under S.R. Scheme at Dindoshi, bearing CTS No. 827D/4, Dindoshi, CTS No. 827D/4, Dindoshi, Malad (East), Mur

: SCHEDULE 'B' :							
Item. No.	Std. Specification	Quantity	Description	Rate		Unit	Amount
				In Figure	In words		
1	R2-CS-DD-65, Pg.187, (MCGM's Buildings Schedule/Common Schedule 2018)	29.81	Removing cement plaster of any finish from the wall, complete with racking out the joints to a depth of 20 mm.	147.00	Rupees One Hundred Forty Seven only.	Sq.Mt.	4382.07
2	(It.6, Pg.54, PWD DSR 15-16)	29.81	Providing sand faces plaster externally using approved screened sand in all positions including base coat of 15 mm thick in cement mortar 1:4 using water proofing compound at the rate of 1 Kilogramme per cement bag anc curing the same for not less than two days and keeping the surface of base coat rough to reveive the sand faced treatment not to exceed 8 mm thickness in cement mortar 1:4, finishing the surface by taking out grains and curing for 14 days and scaffolding etc. complete.	623.00	Rupees Six Hundred Twenty Three only.	Sq.Mt.	18571.63
3	R2-CS-DD-71, Pg.187, (MCGM's Buildings Schedule/Common Schedule 2018)	27.00	Removing existing door or windows with frame and shutters and making good etc. to the existing surface.	563.00	Rupees Five Hundred Sixty Three only.	Nos.	15201.00
4	(It.50, Pg.99, PWD DSR 2015-16)	38.88	Providing and fixing in position extruded modular alluminium section two track Sliding Window mounted on rectangular frame of size 63 mm x 38mm x 2.00 mm thick (1.054 Kg/Rmt) made up of two track drain bottom section of size 61 mm x 45 mm x 1.3 mm thick (1.055 kg/Rmt) and top and sides sections of size 61 mm x 31 mm x 1.3 mm thick (0.659 kg./Rmt.) The shutter should be of bearing bottom of size 40 mm x 18 mm x 1.25 mm thick (0.417 Kg/Rmt) top member of size 40 mm x 18 mm x 1.20 mm thick (0.475 kg/Rmt) Interlocking section size of 43 mm x 27 mm x 1.30 mm thick (0.558 kg/Rmt) and handle section of size 43 mm x 18 mm x 1.30 mm thick (0.424 kg./Rmt), selected quality 5.5 mm thick clear glass to be fixed in shutter with neoprene gasket with approved quality PVC rollers, necessary locks, handles, PVC lining and wooden encasement wherever necessary etc. complete without powder coating	4567.00	Rupees Four Thousand Five Hundred Sixty Seven only.	Sq.Mt.	177564.96


Item. No.	Std. Specification	Quantity	Description	Rate		Unit	Amount
				In Figure	In words		
5	R2-CS-SL-12-a, Pg.101, (MCGM's Buildings Schedule/Common Schedule 2018)	18.72	Providing and Fixing MS Safety grill of weight weighing 10 to 15 kg / sqm for windows as per design including fabricating the grill using M.S. square / round bar, flats and angles including painting with one coat of red oxide zinc chromate primer and two coats of synthetic enamel paint of approved colour and brand etc complete as directed.	2021.00	Rupees Two Thousand Twenty One only.	Sq.Mt.	37833.12
6	R2-CS-SS-14, Pg.95, (MCGM's Buildings Schedule/Common Schedule 2018)	38.88	Providing and fixing G.I. crimped wire mesh of required openings of size 25 mm x25 mm or of any size with main and cross wires of 10 gauge approved type as per manufacture's specifications with necessary fittings including painting with one coat of one coat of red oxide zinc chromate primer and two coats of approved synthetic enamel paint etc. complete as directed by Engineer In Charge. (Iron works will be paid separately. The clear visible area of the wire mesh exclusive overlap will be paid for).	1081.00	Rupees One Thousand Eighty One only.	Sq.Mt.	42029.28
7	(It.60(b), Pg.161, PWD DSR 2015-16)	5.00	Shooting of still photographs outdoor and indoor of construction and other works of building, bridges, roads, etc. in district and outside district at any distance. (Still Photo 4" x 6" size)	95.00	Rupees ninety five only.	03 Copies each photo	475.00
						Total Rs.	296,057.06
						Say Rs.	296,057.00

(Rupees Two lakhs Ninety Six thousand Fifty Seven only)

I/We hereby agree to quote _____% Above/Below or At par with the estimated cost put to the tender.

Therefore, the amount (in figure) _____ (in words) _____

Signature of Contractor/s


 Executive Engineer (Dharavi)/SPPL