


**Shivshahi Punarvasan Prakalp Ltd.**  
5<sup>th</sup> Floor, Griha Nirman Bhavan, Bandra (E), Mumbai- 400 051.

**QUOTATION NOTICE**

1. Quotations in sealed covers are invited from the Contractors so as to reach the office of the undersigned at Shivshahi Punarvasan Prakalp Ltd. Griha Nirman Bhavan, Bandra (E), Mumbai- 400 051 **on or before 18/10/2016 upt 3.00 p.m. for the work of providing & fixing G.I. chainlinked fencing near sub station between back side of Bldg. no. 6 & 5 under S.R Scheme at Rahul Nagar, Sewri, Mumbai.**
2. **The estimated cost of the work is Rs. 2,89,239.00** (Rupees Two Lakhs Eighty Nine Thousand Two Hundred Thirty Nine only).
3. The quotations in sealed cover shall be addressed to the Executive Engineer (City), Shivshahi Punarvasan Prakalp Ltd., Griha Nirman Bhavan, Bandra (East), Mumbai- 400 051. The blank quotations can be downloaded from the tender section of SPPL website [www.sppl.biz](http://www.sppl.biz) from **07/10/2016 to 18/10/2016 upto 2.00 p.m.**
4. The quotationer shall quote in ink his percentage offer above/below or at par the estimated cost both in figures and words. The quotation should be submitted in a single sealed Envelope containing forwarding letter, quotation notice and duly filled Schedule-B and signed on each page.
5. The name of work for which quotations have been given should be stated clearly on the envelope containing the quotation and name of Contractor should be written on lower left of envelope.
6. The sealed quotation will be received by the office of Executive Engineer (City)/SPPL, 5<sup>th</sup> floor, Griha Nirman Bhavan, Bandra (East), Mumbai – 400 051 upto **3.00 p.m.** by **18/10/2016** and will be opened at **3.30 p.m.** on the same day as far as possible in the presence of the contractors/their representatives whosoever remain present at that time.
7. The quantities as shown in Schedule 'B' are approximate. The payment will be made as per actual quantity of work done.
8. The acceptance of quotation shall rest with the competent authority who reserves the right to reject any or all the quotations without assigning any reason for doing so.
9. The quotation submitted by the quotationer shall be binding on him for a period of 90 days from the last date of receipt of quotation.
10. No alternation in the form of quotation or schedule of quantities, specifications shall be entertained.
11. The entire work is to be completed within **180 days.**
12. The work shall be carried out in accordance with I.S. specifications for the particular items and as per the detailed specifications mentioned in Schedule-B.

13. The rates quoted shall be inclusive of all taxes, Octroi Duty and free delivery at site of work and nothing extra shall be paid on any account.
14. The quotationer is advised to visit and examine the site of work and its surroundings before quoting the rate and acquaint themselves with the site conditions.
15. The contractor will have to make his/ their own arrangement at his/their cost for office and stores and safeguard the materials brought on the work and the materials issued by the department if any.
16. The contractor shall provide all labors, tools, pegs, watering and all other materials as required for line out and setting out the layout etc. for the work without claiming any payment.
17. After the completion of the work, the contractor shall remove forthwith all his/ their serviceable and un-serviceable materials from site of work and other debris shall be dumped and leveled as ordered within the scope of work if so ordered without any extra cost.
18. No escalation shall be paid to the contractor.
19. The successful quotationer shall have to enter into A-1 Agreement with the Executive Engineer (City)/SPPL as per the rules in force.

  
Executive Engineer (City),  
Shivshahi Punarvasan Prakalp Ltd.  
Mumbai- 400 051.

---

No. SPPL/ GM(Engg)/EE(City)/ <sup>1486</sup> /2016,  
Office of the Executive Engineer  
Shivshahi Punarvasan Prakalp Ltd.  
Griha Nirman Bhavan, Bandra (E),  
Mumbai- 400 051.

Date : 7 / 10 / 2016

**Issued to :**

M/s. \_\_\_\_\_

Copy submitted to G.M. (Finance)/SPPL for information.

Copy submitted to Dy.CE/SPPL for information.

Copy f.w.c's to Accounts Officer/SPPL for information.

Copy to D.E./SPPL for information & necessary action

Copy to Notice Board/SPPL.

Copy to M/s. IMPAQ TECHNOLOGIES PVT. LTD. for publishing quotation notice along with Schedule-B on SPPL website.

NAME OF WORK : S.R Scheme at Rahul Nagar, Sewri, Mumbai

--- Providing & fixing G.I. chainlinked fencing near sub station between back side of Bldg. no. 6 & 5.

: SCHEDULE 'B' :							
Item. No.	Std. Specification	Quantity	Description	Rate		Unit	Amount
				In Figure	In words		
1	Bd/A-1, P.259 (It.1, Pg.5, PWD DSR 2015-16)	3.87	Excavation for foundation in earth, soil of all types, sand, gravel and soft murum including removing the excavated materials upto a distance of 50 meters beyond the building area and lift upto 1.50 metres, stacking and spreading as directed including dewatering unless provided elsewhere, preparing the bed for the foundation and necessary backfilling, ramming, watering complete excluding shoring and strutting.	239.00	Rs. Two Hundred Thirty Nine only.	Cu.Mt.	924.93
2	Bd/A-12, P.264 (It.10, Pg.7, PWD DSR 2015-16)	1.07	Providing dry trap / rubble stone soling 15cm to 20cm thick including hand packing and compacting etc. complete.	915.00	Rs. Nine Hundred Fifteen only.	Cu.Mt.	979.05
3	Bd/E-1, P-287 (It.-1(d), Pg-13, PWD DSR 2015-16)	0.47	Providing and laying in position in situ plain cement concrete M-15 with minimum cement content of 320 Kg./Cum as per IS 456-2000 for accelerate, retard setting of concrete improve workability without imparing strength and durability. The rates shall includes bailing out water manually centering, shuttering, compacting by vibrator and curing (Excluding reinforcement) etc. complete.	6753.00	Rs. Six Thousand Seven Hundred Fifty Three only.	Cu.Mt.	3173.91
4	Bd/E-2, P-288 (It.-4, Pg-14, PWD DSR 2015-16)	2.33	Providing and casting in situ plain cement concrete M-15 grade with minimum cement content 320 Kg./cum. as per approved mix design as per BIS 456-2000 by Engineer-in-charge for <b>bed blocks</b> , foundation blocks and such other items including admixtures to accelerate, retard setting of concrete to improve workability without imparing strength and durability. The rates shall includes bailing out water manually centering, shuttering, compacting by vibrator and curing (Excluding reinforcement) etc. complete.	6882.00	Rs. Six Thousand Eight Hundred Eighty Two only.	Cu.Mt.	16035.06
5	(It. No. FMB 16.11 page B-80 of MCGM FMR)	40.25	Providing and fixing wrought iron galvanised pipe with all fittings complete as required size 100 mm.	1542.00	Rs. One Thousand Five Hundred Forty Two only.	Rmt.	62065.50
6	(It. No. FMB 11.63 page B-54 of MCGM FMR)	1.140	Providing and fixing in position light weight M.S. Angles, tees, plates, rolled steel beams, joist and stanchions etc. including all labour and meterial in hoisting, fixing with bolts and nuts or by welding etc. complete including 3 coats of syn. Ena. paints (steel to be supplied by Municipal Corporation)	86568.00	Rs. Eighty Six Thousand Five Hundred Sixty Eight only.	M.T.	98687.52


Item No.	Std. Specification	Quantity	Description	Rate		Unit	Amount
				In Figure	In words		
7	(It. No. FMB 11.19 page B-51 of MCGM FMR)	54.58	Providing and fixing G.I. chain linked fencing of 6 gauge to 8 gauge of 50 mmx 50mm size of opening of the chain link with necessary fittings etc., two coats of approved Syn. Ena. Paint on one coat of primer etc. complete as directed and specified. (Iron work will be paid separately. Clear visible area of chain linked exclusive of overlaps will be paid for).	839.00	Rs. Eight Hundred Thirty Nine only.	Sq.Mt.	45792.62
8	(It.16, Pg.39, PWD DSR 2015-16)	87.87	Removing any kind of debris including loading in truck and conveying to dumping point approved by BMC, unloading, spreading etc. complete. With all leads and lifts.	690.00	Rs. Six hundred ninety only.	Cu.Mt.	60630.30
9	(It.60(b), Pg.161, PWD DSR 2015-16)	10.00	Shooting of still photographs outdoor and indoor of construction and other works of building, bridges, roads, etc. in district and outside district at any distance. (Still Photo 4" x 6" size)	95.00	Rs. Ninety Five only.	03 Copies each photo	950.00
						<b>Total Rs.</b>	<b>289,238.89</b>
						<b>Say Rs.</b>	<b>289,239.00</b>

**(Rupees Two Lakhs Eighty Nine Thousand Two Hundred Thirty Nine only)**

I/We hereby agree to quote \_\_\_\_\_% Above/Below or At par with the estimated cost put to the tender.

Therefore, the amount (in figure) \_\_\_\_\_ (in words) \_\_\_\_\_

Signature of Contractor/s

  
 Executive Engineer (City)/SPPL