


Shivshahi Punarvasan Prakalp Ltd.

5th Floor, Griha Nirman Bhavan, Bandra (E), Mumbai- 400 051.

QUOTATION NOTICE

1. Quotations in sealed covers are invited from the Contractors so as to reach the office of the undersigned at Shivshahi Punarvasan Prakalp Ltd. Griha Nirman Bhavan, Bandra (E), Mumbai- 400 051 **on or before 05/12/2016 upt 3.00 p.m. for carrying out rectification work, providing & applying internal water bound distemper paint and external acrylic based exterior paint for ground floor structure consisting shop no. 1 to 5 in S1 Bldg. Type IV under S.R Scheme at Turbhe Mandale, Mankhurd, Mumbai.**
2. **The estimated cost of the work is Rs. 2,99,164.00** (Rupees Two Lakhs Ninety Nine Thousand One Hundred Sixty Four only).
3. The quotations in sealed cover shall be addressed to the Executive Engineer (Suburbs), Shivshahi Punarvasan Prakalp Ltd., Griha Nirman Bhavan, Bandra (East), Mumbai- 400 051. The blank quotations can be downloaded from the tender section of SPPL website www.sppl.biz from **24/11/2016 to 05/12/2016 upto 2.00 p.m.**
4. The quotationer shall quote in ink his percentage offer above/below or at par the estimated cost both in figures and words. The quotation should be submitted in a single sealed Envelope containing forwarding letter, quotation notice and duly filled Schedule-B and signed on each page.
5. The name of work for which quotations have been given should be stated clearly on the envelope containing the quotation and name of Contractor should be written on lower left of envelope.
6. The sealed quotation will be received by the office of Executive Engineer (Suburbs)/SPPL, 5th floor, Griha Nirman Bhavan, Bandra (East), Mumbai – 400 051 upto **3.00 p.m.** by **05/12/2016** and will be opened at **3.30 p.m.** on the same day as far as possible in the presence of the contractors/their representatives whosoever remain present at that time.
7. The quantities as shown in Schedule 'B' are approximate. The payment will be made as per actual quantity of work done.
8. The acceptance of quotation shall rest with the competent authority who reserves the right to reject any or all the quotations without assigning any reason for doing so.
9. The quotation submitted by the quotationer shall be binding on him for a period of 90 days from the last date of receipt of quotation.
10. No alternation in the form of quotation or schedule of quantities, specifications shall be entertained.
11. The entire work is to be completed within **180 days**.
12. The work shall be carried out in accordance with I.S. specifications for the particular items and as per the detailed specifications mentioned in Schedule-B.

13. The rates quoted shall be inclusive of all taxes, Octroi Duty and free delivery at site of work and nothing extra shall be paid on any account.
14. The quotationer is advised to visit and examine the site of work and its surroundings before quoting the rate and acquaint themselves with the site conditions.
15. The contractor will have to make his/ their own arrangement at his/their cost for office and stores and safeguard the materials brought on the work and the materials issued by the department if any.
16. The contractor shall provide all labors, tools, pegs, watering and all other materials as required for line out and setting out the layout etc. for the work without claiming any payment.
17. After the completion of the work, the contractor shall remove forthwith all his/ their serviceable and un-serviceable materials from site of work and other debris shall be dumped and leveled as ordered within the scope of work if so ordered without any extra cost.
18. No escalation shall be paid to the contractor.
19. The successful quotationer shall have to enter into A-1 Agreement with the Executive Engineer (Suburbs)/SPPL as per the rules in force.


Executive Engineer (Suburbs),
Shivshahi Punarvasan Prakalp Ltd.
Mumbai- 400 051.

No. SPPL/ GM(Engg)/EE(Suburbs)/1764/2016,
Office of the Executive Engineer
Shivshahi Punarvasan Prakalp Ltd.
Griha Nirman Bhavan, Bandra (E),
Mumbai- 400 051.

Date :24/ 11 / 2016

Issued to :

M/s. _____

Copy submitted to G.M. (Finance)/SPPL for information.

Copy submitted to Dy.CE/SPPL for information.

Copy f.w.c's to Accounts Officer/SPPL for information.

Copy to D.E./SPPL for information & necessary action

Copy to Notice Board/SPPL.

✓ Copy to M/s. IMPAQ TECHNOLOGIES PVT. LTD. for publishing quotation notice along with Schedule-B on SPPL website.

NAME OF WORK : S.R Scheme at Turbhe Mandale, Mankhurd, Mumbai.

--- Carrying out rectification work, providing & applying internal water bound distemper paint and external acrylic based exterior paint for ground floor structure consisting shop no. 1 to 5 in S1 Bldg. Type IV.

| : SCHEDULE 'B' : | | | | | | | |
|------------------|--|----------|--|-----------|--|--------|----------|
| Item. No. | Std. Specification | Quantity | Description | Rate | | Unit | Amount |
| | | | | In Figure | In words | | |
| 1 | CS-RM-34, Pg.156, (MCGM's Buildings Schedule/Common Schedule 2013) | 398.26 | Removing white or colour wash by scrapping and sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete. | 7.00 | Rupees Seven only. | Sq.Mt. | 2787.82 |
| 2 | CS-PN-2, Page 48 of MCGM's Building Schedule/Common Schedule 2013 | 408.99 | Providing and applying first single coat of approved primer and two coats of dry distemper paint (water bound distemper) of an approved make and colour as per manufacturers specifications to any surface, at all height and locations as directed including scaffolding, cleaning and preparing surfaces for painting with broom, coir and sand paper if necessary or by any other approved means, etc. complete as directed by Engineer-incharge. | 77.00 | Rupees Seventy Seven only. | Sq.Mt. | 31492.23 |
| 3 | It.35, Pg.65, PWD DSR 2015-16) | 82.24 | Washing and cleaning any kind of tiled flooring, dado with washing powder and water. (As directed by Engineer in Charge) | 13.85 | Rupees Thirteen point Eighty Five only | Sq.Mt. | 1139.02 |
| 4 | CS-DD-65, Pg.167, (MCGM's Buildings Schedule/Common Schedule 2013) | 10.73 | Removing cement plaster of any finish from the wall, complete with racking out the joints to a depth of 20 mm. | 87.00 | Rupees Eighty Seven only. | Sq.Mt. | 933.51 |
| 5 | Bd/L-2, P-368 (It.-2(b), Pg-53, PWD DSR 2015-16) | 10.73 | Providing internal cement plaster 12 mm thick in a single coat in in cement mortar 1:4 without neeru finish to concrete or brick surfaces in all positions including scaffolding and curing complete. | 221.00 | Rupees Two Hundred Twenty One only. | Sq.Mt. | 2371.33 |

| Item. | Std. | Quantity | Description | Rate | | Unit | Amount |
|-------|--|----------|--|---------|---|--------|---------|
| 6 | Bd/L-10, P-370 (lt. 8, Pg-54, PWD DSR 2015-16) | 10.73 | Providing neeru finish to plastered surfaces in all position including scaffolding and curing complete. | 55.00 | Rupees Fifty Five only. | Sq.Mt. | 590.15 |
| 7 | CS-DD-19-a, Pg.164, (MCGM's Buildings Schedule/Common Schedule 2013) | 2.60 | Dismantling tile work in floors and roofs laid in cement mortar including stacking material within 50 metres lead. For thickness of tiles 10 mm to 25 mm | 27.00 | Rupees Twenty Seven only | Sq.Mt. | 70.20 |
| 8 | lt.No.6, Pg.36) of PWD DSR 2015-16 | 2.60 | Providing waterproof plaster in W.C. and bath 20 mm thick for dado in cement mortar 1:3 with neat finishing, floating using waterproofing compound at the rate of One kg. per bag of cement, etc. complete | 381.00 | Rupees Three Hundred Eighty One only. | Sq.Mt. | 990.60 |
| 9 | lt.No.7, Pg.36) of PWD DSR 2015-16 | 1.17 | Providing waterproofing in W.C. and bath including brick bat coba in all positions consisting of specialised materials as per manufacturer's specifications and covering ten years guarantee on requisite stamp paper including all leads, lifts and curing etc. complete. | 4727.00 | Rupees Four Thousand Seven Hundred Twenty Seven only. | Cu.Mt. | 5530.59 |
| 10 | (lt.No.8, Pg.36) of PWD DSR 2015-16 | 2.60 | Providing waterproof bedding 25 mm thick for flooring of bath and W.C. in cement mortar 1:3 using 1 kg of waterproofing compound of approved make and manufacture per bag of cement including leveling, curing, etc. complete. | 484.00 | Rupees Four Hundred Eighty Four only. | Sq.Mt. | 1258.40 |
| 11 | Bd/M-12, P-385 (lt.-11(a), Pg-59, PWD DSR 2015-16) | 2.60 | Providing and laying white glazed tile 200 x 100 mm in size and 8 to 9.5 mm thick for flooring in required positions laid on a bed of 1:4 cement mortar including neat cement float, all special required like round, edge tiles, corner cups, etc. filling joints with white cement slurry, curing and cleaning complete. | 1183.00 | Rupees One Thousand One Hundred Eighty Three only. | Sq.Mt. | 3075.80 |

| Item. | Std. | Quantity | Description | Rate | | Unit | Amount |
|-------|--|----------|---|---------|---|--------|---------|
| 12 | Bd/M-13, P-386 (It.-12(a), Pg-59, PWD DSR 2015- 16) | 3.45 | Providing and fixing white glazed tile of 200 x 100 mm in size and about 6.5 mm thick for dado and skirting in required positions fixed on plaster of cement mortar 1:4 including neat cement float, all special required like round, edge tiles, corner cups etc. filling joints with neat cement slurry mixed with approved shade of pigment to match the colour of tiles, curing and cleaning etc. complete. | 1278.00 | Rupees One Thousand Two Hundred Seventy Eight only. | Sq.Mt. | 4409.10 |
| 13 | CS-SL-12-a, Page 82 of MCGM's Building Schedule/Comm n Schedule 2013 | 5.76 | Providing and Fixing MS Safety Grill weighing 10 to 15 kg / sqm of weight specified below for windows as per design including fabricating the grill using M.S. square / round bar, flats and angles including painting with one coat of red oxide zinc chromate primer and two coats of synthetic enamel paint of approved colour and brand etc complete as directed. | 1632.00 | Rupees One Thousand Six Hundred Thirty Two only. | Sq.Mt. | 9400.32 |
| 14 | (Bd/M-9, P-383, It.No.10(a), Pg.59) of PWD DSR 2015-16 | 0.31 | Providing and fixing plain cement tiles for dado and skirting in required position fixed on base plaster of cement mortar 1:4 including, filling joints with neat cement slurry, curing, rubbing, polishing and cleaning complete. | 633.00 | Rupees Six Hundred Thirty Three only. | Sq.Mt. | 196.23 |
| 15 | (It.-56, Pg-101, PWD DSR 2015- 16) | 5.76 | Replacing by providing and fixing 3 mm thick rubbed glass of doors and windows etc. including putty complete. | 504.00 | Rupees Five Hundred Four only. | Sq.Mt. | 2903.04 |
| 16 | (It.-63, Pg-140, PWD DSR 2015- 16) | 1000.00 | Providing and fixing High Density Polyethylene UV stabilized water storage tank including conveying and hoisting in position confirming to I.S. 12701, with all leads and lifts of making necessary connection, testing and all required accessories including providing steel ladder as per M.C.G.M. requirement etc. complete. (Prior approval of sample by Executive Engineer is necessary before use). | 7.00 | Rupees Seven only. | Ltr. | 7000.00 |
| 17 | CS-PN-4-a, Page 48 of MCGM's Building Schedule/Comm n Schedule 2013 | 52.90 | Providing and applying first single coat of approved primer and two coats of synthetic enamel paint/flat oil paint of an approved make and colour as per manufacturers specifications to surfaces specified below, at all height and locations as directed including scaffolding, cleaning and preparing surfaces for painting by any approved means etc. complete as directed by Engineer-in-charge. For Steel work. | 132.00 | Rupees One Hundred Thirty Two only. | Sq.Mt. | 6982.80 |

| Item. | Std. | Quantity | Description | Rate | | Unit | Amount |
|-------|--|----------|--|--------|---------------------------------------|---------|----------|
| 18 | CS-PN-12-a, Page 50 of MCGM's Building Schedule/Common Schedule 2013 | 195.35 | Providing and applying first single coat of approved primer and two coats of anti-algal, anti-fungal, exterior paint <i>by using acrylic based exterior paint</i> of an approved make and colour as per manufacturers specifications to any surface, upto 10m height from ground level and at all locations as directed including preparing surfaces for painting by any approved means, watering, scaffolding, cleaning and curing etc. complete as directed by Engineer-in-charge. | 193.00 | Rupees One Hundred Ninety Three only. | Sq.Mt. | 37702.55 |
| 19 | As per wording of Item (Rate Analysis) | 5.00 | Providing and fixing 7 lever Godrej lock with three keys, etc. complete. | 650.00 | Rupees Six Hundred Fifty only. | Per No. | 3250.00 |
| 20 | CS-DD-35-b, Page 165, (MCGM's Buildings Schedule/Common Schedule 2013) | 52.27 | Dismantling precast concrete or stone slabs in walls, partition walls, etc. including stacking within 50 meters lead, thickness above 40 mm upto 75 mm. | 164.00 | Rupees One Hundred Sixty four only. | Sq.Mt. | 8572.28 |
| 21 | CS-FL-38-b, Page 63 (MCGM's Buildings Schedule/Common Schedule 2013) | 108.90 | Providing and fixing polished natural stone slab as specified below of approved quality, pattern and colour for treads with kadappa stone for width upto 300 mm including preparing the surface and levelling in the desired line, in cement mortar 1:4, cement float, machine cutting, levelling, jointing, smooth cement plastering along the side to match the existing surface in cement mortar 1:3, filling the joints with neat cement or pigment mixed with cement, polishing, finishing, curing, etc. complete as directed by Engineer In Charge. | 591.00 | Rupees Five Hundred Ninety One only. | R.Mt. | 64359.90 |
| 22 | CS-FL-21-m, Page 58 (MCGM's Buildings Schedule/Common Schedule 2013) | 108.90 | Providing and fixing polished natural stone tiles/ slab as specified below of approved quality, pattern and colour for flush/projected skirting and risers 15 to 20mm thk. Kadappa stone for height upto 300 mm including preparing the surface and levelling in the desired line, backing of 20 thk. cement mortar in proportion 1:3, square cut top edge or chamfered top edge in cement mortar 1:3, cement float, machine cutting, levelling, jointing, filling the joints with neat cement or pigment mixed with cement, polishing, finishing, curing, etc. complete as directed by Engineer In Charge | 321.00 | Rupees Three Hundred Twenty One only. | R.Mt. | 34956.90 |

| Item. | Std. | Quantity | Description | Rate | | Unit | Amount |
|-------|--|----------|---|---------|--|--------|----------|
| 23 | Bd/A-1, P.259 (lt.1(a), Pg.5, PWD DSR 2015-16) | 10.71 | Excavation for foundation in earth, soil of all types, sand, gravel and soft murum including removing the excavated materials upto a distance of 50 meters beyond the building area and lift upto 1.50 metres, stacking and spreading as directed including dewatering unless provided elsewhere, preparing the bed for the foundation and necessary backfilling, ramming, watering complete excluding shoring and strutting. | 239.00 | Rupees Two Hundred Thirty Nine only. | Cu.Mt. | 2559.69 |
| 24 | Bd/A-12, P.264 (lt.10, Pg.7, PWD DSR 2015-16) | 4.93 | Providing dry trap / rubble stone soling 15cm to 20cm thick including hand packing and compacting etc. complete. | 915.00 | Rupees Nine Hundred Fifteen only. | Cu.Mt. | 4510.95 |
| 25 | Bd/E-1, P-287 (lt.1(c), Pg.13, PWD DSR 15-16) | 2.14 | Providing and laying in situ plain cement concrete M-10 with minimum cement content of 220 Kg./Cum as per IS 456-2000 for foundation and bedding including admixtures to accelerate, retard setting of concrete improve workability without imparing strength and durability. The rates shall includes bailing out water manually centering, shuttering, compacting by viderator and curing (Excluding reinforcement) etc. complete. | 6018.00 | Rupees Six Thousand Eighteen only. | Cu.Mt. | 12878.52 |
| 26 | Bd/E-2, P-288 (lt.- 4, Pg-14, PWD DSR 2015-16) | 3.21 | Providing and casting in situ plain cement concrete M-15 grade with minimum cement content 320 Kg./cum. as per approved mix design as per BIS 456-2000 by Engineer-in-charge for bed blocks , foundation blocks and such other items including admixtures to accelerate, retard setting of concrete to improve workability without imparing strength and durability. The rates shall includes bailing out water manually centering, shuttering, compacting by vibrator and curing (Excluding reinforcement) etc. complete. | 6882.00 | Rupees Six Thousand Eight Hundred Eighty Two only. | Cu.Mt. | 22091.22 |
| 27 | (Bd/M-8, P-383, lt.No.9(a), Pg.59) of PWD DSR 2015-16 | 21.42 | Providing and laying plain cement tiles of size 25 cm x 25 cm for flooring laid on a bed of cement mortar 1:4 including neat cement float, filling joints with neat cement slurry, curing, machine polishing and cleaning etc. complete (without border/ with border/ with pattern of cement tiles of approved colour). | 525.00 | Rupees Five Hundred Twenty Five only. | Sq.Mt. | 11245.50 |

| Item. | Std. | Quantity | Description | Rate | | Unit | Amount |
|------------------|--|----------|--|---------|---|----------------------|-------------------|
| 28 | (It.16, Pg.39, PWD DSR 2015-16) | 12.89 | Removing any kind of debris including loading in truck and conveying to dumping point approved by BMC, unloading, spreading etc. complete. With all leads and lifts. | 690.00 | Rupees Six Hundred Ninety only. | Cu.Mt. | 8894.10 |
| 29 | (It.60(b), Pg.161, PWD DSR 2015-16) | 5.00 | Shooting of still photographs outdoor and indoor of construction and other works of building, bridges, roads, etc. in district and outside district at any distance. (Still Photo 4" x 6" size) | 95.00 | Rupees Ninety Five only. | 03 Copies each photo | 475.00 |
| 30 | CS-FL-40-m, Page 65 of MCGM's Building Schedule/Common Schedule 2013 | 3.74 | Providing and fixing polished natural stone tiles 25 to 30 mm thk. Kadappa stone for width upto 300 mm of approved quality, pattern and colour for sill and jambs including preparing the surface and levelling in the desired line, cement mortar 1:3 bedding or backing, cement float, machine cutting, leveling, jointing, smooth cement plastering along the sides to match the existing surface in cement mortar 1:3, filling the joints with neat cement or pigment mixed with | 321.00 | Rupees Three Hundred Twenty One only. | Rmt. | 1200.54 |
| 31 | (It.82, Pg.107, PWD DSR 2015-16) | 3.15 | Providing & fixing 30 mm thick single leaf door shutter of approved quality and make of 1.5 mm thick P.V.C. Sheets on both sides filled with PUF (Poly urethane foam) with three numbers of bright finished brass butt hinges (100 x 70 x 4 mm size) with brass screws, chromium plated fixtures and fastenings such as one number of 16 mm and 300 mm long aldrop, one number of 250 x 25 x 5 mm door latch, two numbers of 100 mm size handles etc. complete. | 1694.00 | Rupees One Thousand Six Hundred Ninety Four only. | Sq.Mt. | 5336.10 |
| Total Rs. | | | | | | | 299,164.39 |
| Say Rs. | | | | | | | 299,164.00 |

(Rupees Two lakhs Ninety Nine Thousand One Hundred Sixty Four only)

I/We hereby agree to quote _____% Above/Below or At par with the estimated cost put to the tender.

Therefore, the amount (in figure) _____ (in words) _____

Signature of Contractor/s


 Executive Engineer (Suburbs)/SPPL