Shivshahi Punarvasan Prakalp Ltd.

5th Floor, Griha Nirman Bhavan, Bandra (E), Mumbai- 400 051.

QUOTATION NOTICE

- 1. Quotations in sealed covers are invited from the Contractors so as to reach the office of the undersigned at Shivshahi Punarvasan Prakalp Ltd. Griha Nirman Bhavan, Bandra (E), Mumbai- 400 051 on or before 02/05/2018 upto 3.00 p.m. for the work of Providing antitermite treatment to the sides of flooring of the tenements—and around the pheriphery of the existing building no. SH-6, washing & cleaning of 69 T/s. and cleaning & disinfecting suction tank, overhead tank & flushing tank of Bldg. No. SH-6 under S.R. Scheme at SHED COMPLEX, Dharavi, Mumbai.
- 2. The estimated cost of the work is Rs. 1,89,936.00 (Rupees One Lakh Eighty Nine Thousand Nine Hundred Thirty Six only).
- 3. The quotations in sealed cover shall be addressed to the Executive Engineer (Dharavi), Shivshahi Punarvasan Prakalp Ltd., Griha Nirman Bhavan, Bandra (East), Mumbai- 400 051. The blank quotations can be downloaded from the tender section of SPPL website www.sppl.biz from 18/04/2018 to 02/05/2018 upto 2.00 p.m.
- 4. The quotationer shall quote in ink his percentage offer above/below or at par the estimated cost both in figures and words. The quotation should be submitted in a single sealed Envelope containing forwarding letter, quotation notice and duly filled Schedule-B and signed on each page.
- The name of work for which quotations have been given should be stated clearly on the envelope containing the quotation and name of Contractor should be written on lower left of envelope.
- 6. The sealed quotation will be received by the office of Executive Engineer (Dharavi)/SPPL, 5th floor, Griha Nirman Bhavan, Bandra (East), Mumbai 400 051 upto **3.00 p.m.** by **02/05/2018** and will be opened at **3.30 p.m.** on the same day as far as possible in the presence of the contractors/their representatives whosoever remain present at that time.
- 7. The quantities as shown in Schedule 'B' are approximate. The payment will be made as per actual quantity of work done.
- 8. The acceptance of quotation shall rest with the competent authority who reserves the right to reject any or all the quotations without assigning any reason for doing so.
- 9. The quotation submitted by the quotationer shall be binding on him for a period of 180 days from the last date of receipt of quotation.
- 10. No alternation in the form of quotation or schedule of quantities, specifications shall be entertained.
- 11. The entire work is to be completed within 180 days.
- 12. The work shall be carried out in accordance with I.S. specifications for the particular items and as per the detailed specifications mentioned in Schedule-B.

- 13. The rates quoted shall be inclusive of all taxes, Octroi Duty and free delivery at site of work and nothing extra shall be paid on any account.
- 14. The quotationer is advised to visit and examine the site of work and its surroundings before quoting the rate and acquaint themselves with the site conditions.
- 15. The contractor will have to make his/ their own arrangement at his/their cost for office and stores and safeguard the materials brought on the work and the materials issued by the department if any.
- 16. The contractor shall provide all labors, tools, pegs, watering and all other materials as required for line out and setting out the layout etc. for the work without claiming any payment.
- 17. After the completion of the work, the contractor shall remove forthwith all his/ their serviceable and un-serviceable materials from site of work and other debris shall be dumped and leveled as ordered within the scope of work if so ordered without any extra cost.
- 18. No escalation shall be paid to the contractor.
- 19. The successful quotationer shall have to enter into A-1 Agreement with the Executive Engineer (Dharavi)/SPPL as per the rules in force.

Executive Engineer (Dharavi), Shivshahi Punarvasan Prakalp Ltd. Mumbai- 400 051.

No. SPPL/GM(Engg)/EE(Dharavi)/456/2018, Office of the Executive Engineer Shivshahi Punarvasan Prakalp Ltd. Griha Nirman Bhavan, Bandra (E), Mumbai-400 051.

Date: 18 / 04 / 2018

Issued to:

Λ/s .	

Copy submitted to G.M. (Finance)/SPPL for information.

Copy submitted to Dy.CE/SPPL for information.

Copy f.w.c's to Accounts Officer/SPPL for information.

Copy to D.E./SPPL, S.E./SPPL for information & necessary action.

Copy to Notice Board/SPPL.

Copy to M/s. IMPAQ TECHNOLOGIES PVT. LTD. for publishing quotation notice along with Schedule-B on SPPL website.

Name of work: S.R. Scheme at SHED COMPLEX, Dharavi, Mumbai.

--- Providing antitermite treatment to the sides of flooring of the tenements and around the pheriphery of the existing building no. SH-6, washing & cleaning of 69 T/s. and cleaning & disinfecting suction tank, overhead tank & flushing tank of Bldg. No. SH-6.

			: SCHEDULE 'B' :				
Item.	Std. Specification	Quantity	Description	Rate		Unit	Amount
No.				In Figure	In words	Unit	AIIIOUIII
1	CS-AT-3, (MCGM's Building Schedule/Comm on Schedule 2013)	5969.00	Providing antitermite treatment confirming to IS-6313 (part-III) to the saides of flooring of the Existing building by punching / drilling the holes of 16 mm dia at a distance of 300mm centre to centre and injecting 150 ml until refusal or to a maximum of 1 Lit. per hole with chloropyrifos EC 20 Emulsion or equivalent of 1% concentration by weight, sealing the hole by filling the putty etc. complete as directed by Engineer-In-charge with 2 years guaranty.		Rs. Twenty Three only.	Per Hole	137287.00
2	CS-AT-2, (MCGM's Building Schedule/Comm on Schedule 2013)	134.50	Providing antitermite treatment around the periphery of the existing building confirming to IS-6313 (part-III) by excavating trenches of 20cm width and exposing the sides of the columns, plinth beams and wall upto a depth of 300mm, rodding for the holes of 300 mm deep and at 150m c/c in the trenches, treating with chloropyrifos EC 20 Emulsion or equivalent of 1% concentration by weight at the total rate of 2.25 Liters per meter including backfilling the trenches etc. complete as directed by Engineer-In-charge covering 2 years guaranty.	Calgaritate - de	Rs. Fifty Three only.	R.Mt.	7128.50
3	lt.54, Pg.160, PWD DSR 2015- 16)	2155.29	Providing mechanised and manual cleaning of open premises by sweeping, scrubbing, Vaccum cleaning, pressure washing etc. with the help of swingo 755 1st or Nilfisk CA 750, Vaccum cleaner and hard Scrubber for Entrance, Corridor, passage area between work stations and staircase.	******	Rs. One point Twenty only.	Sq.Mt.	2586.35
4	lt.35, Pg.65, PWD DSR 2015- 16)	1903.29	Washing and cleaning any kind of tiled flooring, dado with washing powder and water. (As directed by Engineer in Charge)	13.85	Rs. Thirteen point Eighty Five only.	Sq.Mt.	26360.57
5	lt.57. Pg.160, PWD DSR 2015- 16)	480.60	Providing cleaning the window glasses of Residential/ Non Residential Govt Building manually and with the help of Back pack Vaccum cleaner and glass cleaning kit etc. complete.	5.00	Rs. Five only.	Sq.Mt.	2403.00

Item. No.	Std.	Quantity	Description	Rate		I I to 16	Δ
	Specification			In Figure	In words	Unit	Amount
6	(It.81, Pg.143, PWD DSR 2015 - 16)	82368.75	Cleaning existing water tank with cold and hot water by jetting pressure machine, using SAF-H-20 (Ayurvedic anti bacteria solution) or equivalent wipping all sides with duster including using ultra voilet rays for disinfections cleaning etc. complete.		Rs. Zero point Twelve only.	Ltr.	9884.25
7	SWD-157, Page 22 (MCGM's SWD Schedule 2013)	2.00	Extra for pumping out water from trenches by 10 H.P. pump per shift of 8 hrs. (item to be operated in abnormal conditions with permission of competent authority)	1668.00	Rs. One Thousand Six hundred Sixty Eight only.	Shift	3336.00
8	(lt.60(b), Pg.161, PWD DSR 2015- 16)	10.00	Shooting of still photographs outdoor and indoor of construction and other works of building, bridges, roads, etc. in district and outside district at any distance. (Still Photo 4" x 6" size)		Rs. Ninety Five only.	03 Copies each photo	950.00
					Total Rs.		189,935.66
					Say Rs.		189,936.00

(Rupees One Lakh Eighty Nine Thousand Nine Hundred Thirty Six only)

Signature of Contractor/s

Executive Engineer (Dharavi)/SPPL