## Shivshahi Punarvasan Prakalp Ltd.

5<sup>th</sup> Floor, Griha Nirman Bhavan, Bandra (E), Mumbai- 400 051.

## **QUOTATION NOTICE**

- 1. Quotations in sealed covers are invited from the Contractors so as to reach the office of the undersigned at Shivshahi Punarvasan Prakalp Ltd. Griha Nirman Bhavan, Bandra (E), Mumbai- 400 051 on or before 08/05/2018 upto 3.00 p.m. for the work of P.T.C. tenements under S.R. Scheme under section 33 (14) D of plot bearing CTS No.164 of village Kandivali, at Kandivali (West), Mumbai --- Washing & cleaning vacant 28 P.T.C. tenements, providing & fixing aluminum grill at mid-landing of the staircase, collapsible gate for the entrance at ground floor of 'B' wing.
- 2. The estimated cost of the work is Rs. 1,46,143.00 (Rupees One Lakh Forty Six Thousand One Hundred Forty Three only).
- 3. The quotations in sealed cover shall be addressed to the Executive Engineer (Dharavi), Shivshahi Punarvasan Prakalp Ltd., Griha Nirman Bhavan, Bandra (East), Mumbai- 400 051. The blank quotations can be downloaded from the tender section of SPPL website <a href="https://www.sppl.biz">www.sppl.biz</a> from 27/04/2018 to 08/05/2018 upto 2.00 p.m.
- 4. The quotationer shall quote in ink his percentage offer above/below or at par the estimated cost both in figures and words. The quotation should be submitted in a single sealed Envelope containing forwarding letter, quotation notice and duly filled Schedule-B and signed on each page.
- 5. The name of work for which quotations have been given should be stated clearly on the envelope containing the quotation and name of Contractor should be written on lower left of envelope.
- 6. The sealed quotation will be received by the office of Executive Engineer (Dharavi)/SPPL, 5<sup>th</sup> floor, Griha Nirman Bhavan, Bandra (East), Mumbai 400 051 upto **3.00 p.m.** by **08/05/2018** and will be opened at **3.30 p.m.** on the same day as far as possible in the presence of the contractors/their representatives whosoever remain present at that time.
- 7. The quantities as shown in Schedule 'B' are approximate. The payment will be made as per actual quantity of work done.
- 8. The acceptance of quotation shall rest with the competent authority who reserves the right to reject any or all the quotations without assigning any reason for doing so.
- 9. The quotation submitted by the quotationer shall be binding on him for a period of 180 days from the last date of receipt of quotation.
- 10. No alternation in the form of quotation or schedule of quantities, specifications shall be entertained.
- 11. The entire work is to be completed within 180 days.
- 12. The work shall be carried out in accordance with I.S. specifications for the particular items and as per the detailed specifications mentioned in Schedule-B.

- 13. The rates quoted shall be inclusive of all taxes, Octroi Duty and free delivery at site of work and nothing extra shall be paid on any account.
- 14. The quotationer is advised to visit and examine the site of work and its surroundings before quoting the rate and acquaint themselves with the site conditions.
- 15. The contractor will have to make his/ their own arrangement at his/their cost for office and stores and safeguard the materials brought on the work and the materials issued by the department if any.
- 16. The contractor shall provide all labors, tools, pegs, watering and all other materials as required for line out and setting out the layout etc. for the work without claiming any payment.
- 17. After the completion of the work, the contractor shall remove forthwith all his/ their serviceable and un-serviceable materials from site of work and other debris shall be dumped and leveled as ordered within the scope of work if so ordered without any extra cost.
- 18. No escalation shall be paid to the contractor.
- 19. The successful quotationer shall have to enter into A-1 Agreement with the Executive Engineer (Dharavi)/SPPL as per the rules in force.

Executive Engineer (Dharavi), Shivshahi Punarvasan Prakalp Ltd. Mumbai- 400 051.

No. SPPL/ GM(Engg)/EE(Dharavi)/ 482 /2018, Office of the Executive Engineer Shivshahi Punarvasan Prakalp Ltd. Griha Nirman Bhavan, Bandra (E), Mumbai- 400 051.

Date: 27/04/2018

## Issued to:

S		
·		

Copy submitted to G.M. (Finance)/SPPL for information.

Copy submitted to Dy.CE/SPPL for information.

Copy f.w.c's to Accounts Officer/SPPL for information.

Copy to D.E./SPPL, S.E./SPPL for information & necessary action.

Copy to Notice Board/SPPL.

Copy to M/s. IMPAQ TECHNOLOGIES PVT. LTD. for publishing quotation notice along with Schedule-B on SPPL website.

NAME OF WORK: P.T.C. tenements under S.R. Scheme under section 33 (14) D of plot bearing CTS No.164 of village Kandivali, at kandivali (West), Mumbai.

--- Washing & cleaning vacant 28 P.T.C. tenements, providing & fixing alluminum grill at mid-landing of the staircase, collapsible gate for the entrance at ground floor of 'B' wing.

Item.	Std.	: SCHEDULE 'B' :  Quantity		Rate			
No.	Specification	Quantity	Description	In Figure	In words	Unit	Amount
1	It.54, Pg.160, PWD DSR 2015- 16)	1383.78	Providing mechanised and manual cleaning of open premises by sweeping, scrubbing, Vaccum cleaning, pressure washing etc. with the help of swingo 755 1st or Nilfisk CA 750, Vaccum cleaner and hard Scrubber for Entrance, Corridor, passage area between work stations and staircase.	1.20	Rupees One point twenty only.	Sq.Mt.	1660.54
2	It.35, Pg.65, PWD DSR 2015- 16)	1471.92	Washing and cleaning any kind of tiled flooring, dado with washing powder and water. (As directed by Engineer in Charge)	13.85	Rupees Thirteen point eighty five only.	Sq.Mt.	20386.09
3	It.57, Pg.160, PWD DSR 2015- 16)	254.88	Providing cleaning the window glasses of Residential/ Non Residential Govt. Building manually and with the help of Back pack Vaccum cleaner and glass cleaning kit etc. complete.	5.00	Rupees five only.	Sq.Mt.	1274.40
4	It.90, Pg.110, PWD DSR 2015- 16)	37.94	Providing and fixing alluminium grill/jali of heavy type 50 x 60 mm opening and 10 mm thick weighing 3.10 kg./smt. Of approved quality and design to windows and ventilators including providing alluminium "F" Patti weighing 0.22 kg./Rmt. Etc. complete as per approved drawing or as directed by Engineer in charge.		Rupees Two thousand three hundred seventy one only.	Sq.Mt.	89955.74
5	CS-SL-04, Pg.81, (MCGM's Buildings Schedule/Comm on Schedule 2013)	3.15	Providing and fixing in position collapsible steel gates with vertical channels 20 x 10 x 2 mm & braced with flat iron diagonals 20 x 5 mm size, top & bottom T section 40 x 40 x 6 mm size, 30 mm steel pulleys complete with bolts-nuts, locking arrangements, stoppers, handles and painting with one coat of red oxide zinc chromate primer and two coats of synthetic enamel paint including all labour, materials, tools and equipments, etc complete as directed by Engineer Incharge.		Rupees five thousand six hundred fifty five only.	Sq.Mt.	17813.25

Item. No.	Std. Specification	Quantity	Description	Rate		Unit	Amount
			Description		In words	OIIIL	
6	CS-DD-8-b, Page 163 (MCGM's Common Schedule 2013)		Dismantling doors, windows and clerestory windows (steel or wood) shutter including chowkhats, architrave, holdfasts etc. complete and stacking within 50 metres lead: Of area beyond 3 sq. metres.	140.00	Rupees One hundred forty only.	Each	280.00
7	It.No.102, Pg.115 of PWD DSR 2015-16	3.78	Providing and fixing UPVC Door of size 1.98 m X 0.91 m or of read size and colour along with all accessories like Hinges, Tower Bolts, Aldrop, Screw, Handel, tadi, etc. hollow section of size 150 mm x 31 mm x 1.2 mm UPVC profile with bordar of "U" hollow size section of size 35mm x 35mm x 2mm the corner will be joined with tough plastic of "L" angles at all corners with stainless steel screws etc. complete.		Rupees Three thousand Six hundred fifty seven only.	Sq.Mt.	13823.46
8	(lt.60(b), Pg.161, PWD DSR 2015- 16)	10.00	Shooting of still photographs outdoor and indoor of construction and other works of building, bridges, roads, etc. in district and outside district at any distance. (Still Photo 4" x 6" size)		Rupees Ninety five only.	03 Copies each photo	950.00
					Total Rs.		146,143.48
					Say Rs.		146,143.00

## (Rupees One Lakh Forty Six Thousand One Hundred Forty Three only)

Ve hereby agree to quote% Above	e/Below or At par with the estimated	a cost put to the tender.
Therefore, the amount (in figure)	(in words)	
		te , —

Signature of Contractor/s

Executive Engineer (Dharavi)/SPPL