


Shivshahi Punarvasan Prakalp Ltd.

5th Floor, Griha Nirman Bhavan, Bandra (E), Mumbai- 400 051.

QUOTATION NOTICE

1. Quotations in sealed covers are invited from the Contractors so as to reach the office of the undersigned at Shivshahi Punarvasan Prakalp Ltd. Griha Nirman Bhavan, Bandra (E), Mumbai- 400 051 **on or before 28/05/2018 upt 3.00 p.m. for the work of Providing & fixing chainlinked fencing over compound wall between Railway line side, garden side and amenity plot at Jasmine Mill Compound 'B' wing of PTC Building under S.R. Scheme under regulation 33(14)(D) of DCR 1991 on plot bearing C.S. No. 1/80 of Dharavi Divn. Mahim.**
2. **The estimated cost of the work is Rs. 2,77,587.00** (Rupees Two Lakhs Seventy Seven Thousand Five Hundred Eighty Seven only).
3. The quotations in sealed cover shall be addressed to the Executive Engineer (Dharavi), Shivshahi Punarvasan Prakalp Ltd., Griha Nirman Bhavan, Bandra (East), Mumbai- 400 051. The blank quotations can be downloaded from the tender section of SPPL website www.sppl.biz from **22/05/2018 to 28/05/2018 upto 2.00 p.m.**
4. The quotationer shall quote in ink his percentage offer above/below or at par the estimated cost both in figures and words. The quotation should be submitted in a single sealed Envelope containing forwarding letter, quotation notice and duly filled Schedule-B and signed on each page.
5. The name of work for which quotations have been given should be stated clearly on the envelope containing the quotation and name of Contractor should be written on lower left of envelope.
6. The sealed quotation will be received by the office of Executive Engineer (Dharavi)/SPPL, 5th floor, Griha Nirman Bhavan, Bandra (East), Mumbai – 400 051 upto **3.00 p.m. by 28/05/2018** and will be opened at **3.30 p.m.** on the same day as far as possible in the presence of the contractors/their representatives whosoever remain present at that time.
7. The quantities as shown in Schedule 'B' are approximate. The payment will be made as per actual quantity of work done.
8. The acceptance of quotation shall rest with the competent authority who reserves the right to reject any or all the quotations without assigning any reason for doing so.
9. The quotation submitted by the quotationer shall be binding on him for a period of 90 days from the last date of receipt of quotation.
10. No alternation in the form of quotation or schedule of quantities, specifications shall be entertained.
11. The entire work is to be completed within **180 days.**
12. The work shall be carried out in accordance with I.S. specifications for the particular items and as per the detailed specifications mentioned in Schedule-B.

13. The rates quoted shall be inclusive of all taxes, Octroi Duty and free delivery at site of work and nothing extra shall be paid on any account.
14. The quotationer is advised to visit and examine the site of work and its surroundings before quoting the rate and acquaint themselves with the site conditions.
15. The contractor will have to make his/ their own arrangement at his/their cost for office and stores and safeguard the materials brought on the work and the materials issued by the department if any.
16. The contractor shall provide all labors, tools, pegs, watering and all other materials as required for line out and setting out the layout etc. for the work without claiming any payment.
17. After the completion of the work, the contractor shall remove forthwith all his/ their serviceable and un-serviceable materials from site of work and other debris shall be dumped and leveled as ordered within the scope of work if so ordered without any extra cost.
18. No escalation shall be paid to the contractor.
19. The successful quotationer shall have to enter into A-1 Agreement with the Executive Engineer (Dharavi)/SPPL as per the rules in force.


Executive Engineer (Dharavi),
Shivshahi Punarvasan Prakalp Ltd.
Mumbai- 400 051.

No. SPPL/ GM(Engg)/EE(Dharavi)/⁵⁹/2018,
Office of the Executive Engineer
Shivshahi Punarvasan Prakalp Ltd.
Griha Nirman Bhavan, Bandra (E),
Mumbai- 400 051.

Date : 22 / 05 / 2018

Issued to :

M/s. _____

Copy submitted to G.M. (Finance)/SPPL for information.

Copy submitted to Dy.CE/SPPL for information.

Copy f.w.c's to Accounts Officer/SPPL for information.

Copy to S.E./SPPL, D.E./SPPL for information & necessary action

Copy to Notice Board/SPPL.

✓ Copy to M/s. IMPAQ TECHNOLOGIES PVT. LTD. for publishing quotation notice along with Schedule-B on SPPL website.

NAME OF WORK : S.R. Scheme under regulation 33(14)(D) of DCR 1991 on plot bearing C.S. No. 1/80 of Dharavi Divn. Mahim.
 --- Providing & fixing chainlinked fencing over compound wall between Railway line side,
 garden side and amenity plot at Jasmine Mill Compound 'B' wing of PTC Building.

: SCHEDULE 'B' :							
Item No.	Std. Specification	Quantity	Description	Rate		Unit	Amount
				In Figure	In words		
1	(It.7, Pg.30, PWD DSR 2015-16)	1.40	Pulling down burnt brick masonry (in cement mortar) with plaster including sorting out serviceable bricks and stacking the same and debris separately upto a distance of 50 metres or spreading the debris etc.complete. Spec:(As directed by Engineer in charge).	255.00	Rs.Two hundred fifty five only.	Cu.Mt.	357.00
2	Bd/E-2, P-288 (It.-2(b), Pg-13, PWD DSR 2015-16)	0.21	Providing and laying in position in situ plain cement concrete M-15 grade with minimum cement content 320 kg/cum. As per approved mix design as per IS 456-2000 by Engineer in charge for coping to plinth or parapet, rounded or chamfered as per drawing including admixtures to accelerate/ retard setting of concrete to improve workability without imparing strength and durability. The rates shall includes bailing out water manually centering, shuttering, compacting by vibrator and curing (Excluding reinforcement) etc. complete.	7216.00	Rs. Seven thousand two hundred sixteen only.	Cu.Mt.	1515.36
3	Bd/E-2, P-288 (It.-4, Pg-14, PWD DSR 2015-16)	1.35	Providing and casting in situ cement concrete M-15 of trap metal for bed blocks, foundations block and such other items including bailing out water manually, formwork, compacting, finishing the exposed faces with sufficient minimum thickness of 1:3 cement plaster to give a smooth and even surface or roughening the exposed faces if special finish is to be provided and curing.	6882.00	Rs. Six thousand eight hundred eighty two only.	Cu.Mt.	9290.70
4	(It. No. FMB 11.63 page B-54 of MCGM FMR)	1.95	Providing and fixing in position light weight M.S. Angles, tees, plates, rolled steel beams, joist and stanchions etc. including all labour and meterial in hoisting, fixing with bolts and nuts or by welding etc. complete including 3 coats of syn. Ena. paints (steel to be supplied by Municipal Corporation)	86568.00	Rs. Eighty six thousand five hundred sixty eight only.	M.T.	168807.60
5	(It. No. FMB 11.19 page B-51 of MCGM FMR)	67.57	Providing and fixing G.I. chain linked fencing of 6 gauge to 8 gauge of 50 mmx 50mm size of opening of the chain link with necessary fittings etc., two coats of approved Syn. Ena. Paint on one coat of primer etc. complete as directed and specified. (Iron work will be paid separately. Clear visible area of chain linked exclusive of overlaps will be paid for).	839.00	Rs. Eight hundred thirty nine only.	Sq.Mt.	56691.23


Item. No.	Std. Specification	Quantity	Description	Rate		Unit	Amount
				In Figure	In words		
6	As per wording of item.	63.00	Providing and fixing 450 mm dia. Concertina barbed razer type coil of 19 mm wide ribbon with thickness 5 SWG with antirust coating, fixed to existing U shape angle bracket etc. complete.	440.00	Rs. Four hundred forty only.	RMt.	27720.00
7	(It.6, Pg.54, PWD DSR 15-16)	18.12	Providing sand faces plaster externally using approved screened sand in all positions including base coat of 15 mm thick in cement mortar 1:4 using water proofing compound at the rate of 1 Kilogramme per cement bag anc curing the same for not less than two days and keeping the surface of base coat rough to reveive the sand faced treatment not to exceed 8 mm thickness in cement mortar 1:4, finishing the surface by taking out grains and curing for 14 days and scaffolding etc. complete.	623.00	Rs. Six hundred twenty three only.	Sq.Mt.	11288.76
8	(It.16, Pg.39, PWD DSR 2015-16)	1.40	Removing any kind of debris including loading in truck and conveying to dumping point approved by BMC, unloading, spreading etc. complete. With all leads and lifts.	690.00	Rs. Six hundred ninety only.	Cu.Mt.	966.00
9	(It.60(b), Pg.161, PWD DSR 2015-16)	10.00	Shooting of still photographs outdoor and indoor of construction and other works of building, bridges, roads, etc. in district and outside district at any distance. (Still Photo 4" x 6" size)	95.00	Rs. Ninety five only.	03 Copies each photo	950.00
Total Rs.							277,586.65
Say Rs.							277,587.00

(Rupees Two Lakhs Seventy Seven Thousand Five Hundred Eighty Seven only)

I/We hereby agree to quote _____% Above/Below or At par with the estimated cost put to the tender.

Therefore, the amount (in figure) _____ (in words) _____

Signature of Contractor/s


 Executive Engineer (Dharavi)/SPPL