


Shivshahi Punarvasan Prakalp Ltd.

5th Floor, Griha Nirman Bhavan, Bandra (E), Mumbai- 400 051.

QUOTATION NOTICE

1. Quotations in sealed covers are invited from the Contractors so as to reach the office of the undersigned at Shivshahi Punarvasan Prakalp Ltd. Griha Nirman Bhavan, Bandra (E), Mumbai- 400 051 **on or before 21/06/2018 upt 3.00 p.m. for the work of Cleaning work in 24 Shops in Bldg. No. 2, providing & fixing M.S. Mesh at the top of rolling shutters and G.I. Sheet fencing between Bldg. no. 2 & Bldg. No. 7 under S.R Scheme at Rahul Nagar, Sewri, Mumbai.**
2. **The estimated cost of the work is Rs. 1,78,484.00** (Rupees One Lakh Seventy Eight Thousand Four Hundred Eighty Four only).
3. The quotations in sealed cover shall be addressed to the Executive Engineer (City), Shivshahi Punarvasan Prakalp Ltd., Griha Nirman Bhavan, Bandra (East), Mumbai- 400 051. The blank quotations can be downloaded from the tender section of SPPL website www.sppl.biz from **15/06/2018 to 21/06/2018 upto 2.00 p.m.**
4. The quotationer shall quote in ink his percentage offer above/below or at par the estimated cost both in figures and words. The quotation should be submitted in a single sealed Envelope containing forwarding letter, quotation notice and duly filled Schedule-B and signed on each page.
5. The name of work for which quotations have been given should be stated clearly on the envelope containing the quotation and name of Contractor should be written on lower left of envelope.
6. The sealed quotation will be received by the office of Executive Engineer (City)/SPPL, 5th floor, Griha Nirman Bhavan, Bandra (East), Mumbai – 400 051 upto **3.00 p.m.** by **21/06/2018** and will be opened at **3.30 p.m.** on the same day as far as possible in the presence of the contractors/their representatives whosoever remain present at that time.
7. The quantities as shown in Schedule 'B' are approximate. The payment will be made as per actual quantity of work done.
8. The acceptance of quotation shall rest with the competent authority who reserves the right to reject any or all the quotations without assigning any reason for doing so.
9. The quotation submitted by the quotationer shall be binding on him for a period of 90 days from the last date of receipt of quotation.
10. No alternation in the form of quotation or schedule of quantities, specifications shall be entertained.
11. The entire work is to be completed within **180 days.**
12. The work shall be carried out in accordance with I.S. specifications for the particular items and as per the detailed specifications mentioned in Schedule-B.

13. The rates quoted shall be inclusive of all taxes, Octroi Duty and free delivery at site of work and nothing extra shall be paid on any account.
14. The quotationer is advised to visit and examine the site of work and its surroundings before quoting the rate and acquaint themselves with the site conditions.
15. The contractor will have to make his/ their own arrangement at his/their cost for office and stores and safeguard the materials brought on the work and the materials issued by the department if any.
16. The contractor shall provide all labors, tools, pegs, watering and all other materials as required for line out and setting out the layout etc. for the work without claiming any payment.
17. After the completion of the work, the contractor shall remove forthwith all his/ their serviceable and un-serviceable materials from site of work and other debris shall be dumped and leveled as ordered within the scope of work if so ordered without any extra cost.
18. No escalation shall be paid to the contractor.
19. The successful quotationer shall have to enter into A-1 Agreement with the Executive Engineer (City)/SPPL as per the rules in force .


Executive Engineer (City),
Shivshahi Punarvasan Prakalp Ltd.
Mumbai- 400 051.

No. SPPL/ GM(Engg)/EE(City)/ 707/2018,
Office of the Executive Engineer
Shivshahi Punarvasan Prakalp Ltd.
Griha Nirman Bhavan, Bandra (E),
Mumbai- 400 051.

Date : 15 / 06 / 2018

Issued to :

M/s. _____

Copy submitted to G.M. (Finance)/SPPL for information.

Copy submitted to Dy.CE/SPPL for information.

Copy f.w.c's to Accounts Officer/SPPL for information.

Copy to D.E./SPPL for information & necessary action

Copy to Notice Board/SPPL.

✓ Copy to M/s. IMPAQ TECHNOLOGIES PVT. LTD. for publishing quotation notice along with Schedule-B on SPPL website.

NAME OF WORK : S.R Scheme at Rahul Nagar, Sewri, Mumbai.

--- Cleaning work in 24 Shops in Bldg. No. 2, providing & fixing M.S. Mesh at the top of rolling shutters and G.I. Sheet fencing between Bldg. no. 2 & Bldg. No. 7.

: SCHEDULE 'B' :							
Item. No.	Std. Specification	Quantity	Description	Rate		Unit	Amount
				In Figure	In words		
1	It.54, Pg.160, PWD DSR 2015-16)	1355.30	Providing mechanised and manual cleaning of open premises by sweeping, scrubbing, Vaccum cleaning, pressure washing etc. with the help of swingo 755 1st or Nilfisk CA 750, Vaccum cleaner and hard Scrubber for Entrance, Corridor, passage area between work stations and staircase.	1.20	Rupees One point Twenty only.	Sq.Mt.	1626.36
2	(It.-35, Pg-65, PWD DSR 2015-16)	503.49	Washing and cleaning any kind of tiled flooring, dado with washing powder and water.	13.85	Rupees Thirteen point Eighty Five only.	Sq.Mt.	6973.34
3	CS-SS-14, Page 77 of MCGM's Building Schedule/Common Schedule 2013	35.89	Providing and fixing G.I. crimped wire mesh of required openings of size 25 mm x25 mm or of any size with main and cross wires of 10 gauge approved type as per manufacture's specifications with necessary fittings including painting with one coat of red oxide zinc chromate primer and two coats of approved synthetic enamel paint etc. complete as directed by Engineer In Charge. (Iron works will be paid separately. The clear visible area of the wire mesh exclusive overlap will be paid for).	670.00	Rupees Six Hundred Seventy only.	Sq.Mt.	24046.30
4	Bd/A-1, P.259 (It.1, Pg.5, PWD DSR 2015-16)	0.55	Excavation for foundation in earth, soil of all types, sand, gravel and soft murum including removing the excavated materials upto a distance of 50 meters beyond the building area and lift upto 1.50 metres, stacking and spreading as directed including dewatering unless provided elsewhere, preparing the bed for the foundation and necessary backfilling, ramming, watering complete excluding shoring and strutting.	239.00	Rupees Two Hundred Thirty Nine only.	Cu.Mt.	131.45
5	Bd/A-12, P.264 (It.10, Pg.7, PWD DSR 2015-16)	0.14	Providing dry trap / rubble stone soling 15cm to 20cm thick including hand packing and compacting etc. complete.	915.00	Rupees Nine Hundred Fifteen only.	Cu.Mt.	128.10

Item No.	Std. Specification	Quantity	Description	Rate		Unit	Amount
				In Figure	In words		
6	Bd/E-1, P-287 (It.-1(c), Pg-13, PWD DSR 2015-16)	0.06	Providing and laying in position in situ plain cement concrete M-10 with minimum cement content of 320 Kg./Cum as per IS 456-2000 for accelerate, retard setting of concrete improve workability without imparing strength and durability. The rates shall includes bailing out water manually centering, shuttering, compacting by vibrator and curing (Excluding reinforcement) etc. complete.	6018.00	Rupees Six Thousand Eighteen only.	Cu.Mt.	361.08
7	Bd/E-1, P-287 (It.-1(d), Pg-13, PWD DSR 2015-16)	0.30	Providing and laying in position in situ plain cement concrete M-15 with minimum cement content of 320 Kg./Cum as per IS 456-2000 for accelerate, retard setting of concrete improve workability without imparing strength and durability. The rates shall includes bailing out water manually centering, shuttering, compacting by vibrator and curing (Excluding reinforcement) etc. complete.	6753.00	Rupees Six Thousand Seven Hundred Fifty Three only.	Cu.Mt.	2025.90
8	(It. No. FMB 11.63 page B-54 of MCGM FMR)	0.333	Providing and fixing in position light weight M.S. Angles, tees, plates, rolled steel beams, joist and stanchions etc. including all labour and material in hoisting, fixing with bolts and nuts or by welding etc. complete including 3 coats of syn. Ena. paints (steel to be supplied by Municipal Corporation)	86568.00	Rupees Eighty Six Thousand Five Hundred Sixty Eight only.	M.T.	28827.14
9	Bd/R-5, P-452 (It.4, Pg.85, PWD DSR 2015-16)	21.90	Providing and fixing corrugated galvanised iron sheets of 0.80 mm thickness (22 B.W.G.) for roofing without wind ties including fastening with galvanised iron screws and bolts and bitumen washers as per drawings complete.	694.00	Rupees Six Hundred Ninety Four only.	Sq.Mt.	15198.60
10	(It.16, Pg.39, PWD DSR 2015-16)	65.82	Removing any kind of debris including loading in truck and conveying to dumping point approved by BMC, unloading, spreading etc. complete. With all leads and lifts.	690.00	Rupees Six Hundred Ninety only.	Cu.Mt.	45415.80
11	As per wording of Item	24.00	Minor repairs and servicing of Rolling shutters including removing dirt and old lubricant from the guides, top sides, springs and applying a film of lubricant to the inside surface.	2200.00	Rupees Two Thousand Two Hundred only.	Nos.	52800.00


Item. No.	Std. Specification	Quantity	Description	Rate		Unit	Amount
				In Figure	In words		
12	(It.60(b), Pg.161, PWD DSR 2015-16)	10.00	Shooting of still photographs outdoor and indoor of construction and other works of building, bridges, roads, etc. in district and outside district at any distance. (Still Photo 4" x 6" size)	95.00	Rupees Ninety five only.	03 Copies each photo	950.00
						Total Rs.	178,484.07
						Say Rs.	178,484.00

(Rupees One Lakh Seventy Eight Thousand Four Hundred Eighty Four only)

I/We hereby agree to quote _____% Above/Below or At par with the estimated cost put to the tender.

Therefore, the amount (in figure) _____ (in words) _____

Signature of Contractor/s


 Executive Engineer (City)/SPPL