


## **Shivshahi Punarvasan Prakalp Ltd.**

5<sup>th</sup> Floor, Griha Nirman Bhavan, Bandra (E), Mumbai- 400 051.

### **QUOTATION NOTICE**

1. Quotations in sealed covers are invited from the Contractors so as to reach the office of the undersigned at Shivshahi Punarvasan Prakalp Ltd. Griha Nirman Bhavan, Bandra (E), Mumbai- 400 051 **on or before 17/09/2018 upt 3.00 p.m. for the work of Providing & fixing orissa type W.C. pan, white glazed tiled flooring & dado, providing & applying oil bound distemper paint and providing & fixing UPVC door frame & shutters to W.C. of Ladies & Gent's toilet for shops in Rehab Building no. 5 under S.R Scheme at Rahul Nagar, Sewri, Mumbai.**
2. **The estimated cost of the work is Rs. 2,64,594.00** (Rupees Two Lakhs Sixty Four Thousand Five Hundred Ninety Four only).
3. The quotations in sealed cover shall be addressed to the Executive Engineer (City), Shivshahi Punarvasan Prakalp Ltd., Griha Nirman Bhavan, Bandra (East), Mumbai- 400 051. The blank quotations can be downloaded from the tender section of SPPL website [www.sppl.biz](http://www.sppl.biz) from **06/09/2018 to 17/09/2018 upto 2.00 p.m.**
4. The quotationer shall quote in ink his percentage offer above/below or at par the estimated cost both in figures and words. The quotation should be submitted in a single sealed Envelope containing forwarding letter, quotation notice and duly filled Schedule-B and signed on each page.
5. The name of work for which quotations have been given should be stated clearly on the envelope containing the quotation and name of Contractor should be written on lower left of envelope.
6. The sealed quotation will be received by the office of Executive Engineer (City)/SPPL, 5<sup>th</sup> floor, Griha Nirman Bhavan, Bandra (East), Mumbai – 400 051 upto **3.00 p.m. by 17/09/2018** and will be opened at **3.30 p.m.** on the same day as far as possible in the presence of the contractors/their representatives whosoever remain present at that time.
7. The quantities as shown in Schedule 'B' are approximate. The payment will be made as per actual quantity of work done.
8. The acceptance of quotation shall rest with the competent authority who reserves the right to reject any or all the quotations without assigning any reason for doing so.
9. The quotation submitted by the quotationer shall be binding on him for a period of 90 days from the last date of receipt of quotation.
10. No alternation in the form of quotation or schedule of quantities, specifications shall be entertained.
11. The entire work is to be completed within **180 days**.
12. The work shall be carried out in accordance with I.S. specifications for the particular items and as per the detailed specifications mentioned in Schedule-B.

13. The rates quoted shall be inclusive of all taxes, Octroi Duty and free delivery at site of work and nothing extra shall be paid on any account.
14. The quotationer is advised to visit and examine the site of work and its surroundings before quoting the rate and acquaint themselves with the site conditions.
15. The contractor will have to make his/ their own arrangement at his/their cost for office and stores and safeguard the materials brought on the work and the materials issued by the department if any.
16. The contractor shall provide all labors, tools, pegs, watering and all other materials as required for line out and setting out the layout etc. for the work without claiming any payment.
17. After the completion of the work, the contractor shall remove forthwith all his/ their serviceable and un-serviceable materials from site of work and other debris shall be dumped and leveled as ordered within the scope of work if so ordered without any extra cost.
18. No escalation shall be paid to the contractor.
19. The successful quotationer shall have to enter into A-1 Agreement with the Executive Engineer (City)/SPPL as per the rules in force.

  
Executive Engineer (City),  
Shivshahi Punarvasan Prakalp Ltd.  
Mumbai- 400 051.

---

No. SPPL/ GM(Engg)/EE(City)/ 1075 /2018,  
Office of the Executive Engineer  
Shivshahi Punarvasan Prakalp Ltd.  
Griha Nirman Bhavan, Bandra (E),  
Mumbai- 400 051.

Date : 06 / 09 / 2018

**Issued to :**

M/s. \_\_\_\_\_

Copy submitted to G.M. (Finance)/SPPL for information.

Copy submitted to Dy.CE/SPPL for information.

Copy f.w.c's to Accounts Officer/SPPL for information.

Copy to D.E./SPPL for information & necessary action

Copy to Notice Board/SPPL.

✓ Copy to M/s. IMPAQ TECHNOLOGIES PVT. LTD. for publishing quotation notice along with Schedule-B on SPPL website.



NAME OF WORK : Providing & fixing orissa type W.C. pan, white glazed tiled flooring & dado, providing & applying oil bound distemper paint and providing & fixing UPVC door frame & shutters to W.C. of Ladies & Gent's toilet for shops in Rehab Building no. 5 under S.R Scheme at Rahul Nagar, Sewri, Mumbai.

: SCHEDULE 'B' :							
Item. No.	Std. Specification	Quantity	Description	Rate		Unit	Amount
				In Figure	In words		
1	Bd/W-8, P-587 (It.67, Pg.141 PWD DSR 15-16)	3.00	Removing W.C. pans including disconnecting the sanitary and water supply connections, removing and breaking flooring and bed concrete around pans and removing pan carefully and throwing our the refusal outside etc. complete.	131.00	Rupees one hundred thirty one only.	No.	393.00
2	R2-CC-DD-64, Pg.187, (MCGM's Buildings Schedule/Common Schedule 2018)	9.27	Removing mosaic, cement marble, granites non-slippery, tandur, kotah, shahabad stone or Indian Pattern stone, glazed tiles in flooring and dado including bedding brick bat coba etc., and delivering materials in Ward Office and carting away unserviceable materials.	240.00	Rupees Two hundred forty only.	Sq.Mt.	2224.80
3	R2-CC-DD-65, Pg.187, (MCGM's Buildings Schedule/Common Schedule 2018)	83.15	Removing cement plaster of any finish from the wall, complete with racking out the joints to a depth of 20 mm.	147.00	Rupees one hundred forty seven only.	Sq.Mt.	12223.05
4	R2-CS-WP-38-a, Pg.51, (MCGM's Buildings Schedule/Common Schedule 2018)	4.56	Providing waterproofing treatment through specialized agencies to the dado portion of the R.C.C. side walls upto 1.5 m height from floor area of water closets, bath-rooms, kitchens, washing places, sanitary blocks etc. by giving „INJECTIONS" treatment with waterproofing compound and cement solution. The walls will then be plastered with waterproof cement plaster in 1:4 c.s. 12 mm to 15 mm thk. Finally the walls shall be covered with jointless waterproof plaster in 1:3 c.s. 12 to 15 mm thick finished rough for receiving tiles. The average thickness of complete treatment shall not be less than 25 mm. (The actual treated area will be measured and paid for).	793.00	Rupees seven hundred ninety three only.	Sq.Mt.	3616.08
5	R2-CS-WP-31, Pg.49, (MCGM's Buildings Schedule/Common Schedule 2018)	1.08	Extra for providing additional thickness of brickbats over 100 mm in 1:5 c.s. either due to location of rain water pipes or due to increase in the travel length of flow of rain water or brick bats required in the sunk portion of baths, W.C.s nahani etc. The rate includes for fixing brickbats in C.M., with waterproofing compound as per specification as directed.	8575.00	Rupees eight thousand five hundred seventy five only.	Cu.Mt.	9261.00



Item. No.	Std. Specification	Quantity	Description	Rate		Unit	Amount
				In Figure	In words		
6	R2-CS-PL-05, Pg.34, (MCGM's Buildings Schedule/Common Schedule 2018)	62.91	Providing and applying 12 mm thick internal plaster in cement mortar 1:3 with neeru finish at all heights and locations in one coat for masonry (except stone masonry) and concrete surfaces including racking out joints, hacking of concrete surface, watering, finishing, curing, scaffolding etc. complete.	361.00	Rupees Three hundred sixty one only.	Sq.Mt.	22710.51
7	Bd/V-20, P-559 (It.-18(a), Pg-129, PWD DSR 2015-16 )	3.00	Providing and fixing Orissa type white glazed earthenware 580 mm x 450 mm water closet pan including trap cast iron soil and vent pipes upto the outside face of the wall including 100 mm. Diameter cast iron plug bend, cement concrete bedding, 10 litres capacity H.D.P.E. flushing cistern with fittings, inlet pipe with stop tap, brackets, 32 mm. diameter galvanised iron heavy type flush pipe with fittings and clamps, painting in gray oil paint to the exposed pipes and cutting and making good the walls and floors etc. complete (Excluding waterproof brick bat coba)	8038.00	Rupees Eight thousand thirty eight only.	No.	24114.00
8	R2-CS-FL-07-a, Pg.63, (MCGM's Buildings Schedule/Common Schedule 2018)	2.70	Providing and laying 8mm thk. ceramic tiles Light coloured glazed ceramic tiles conforming to I.S.15622-2006 for flooring of an approved, quality, make, size and pattern /design, for flooring including cement mortar bedding of 25 mm thick in 1:4 proportion, neat cement float, cutting, leveling, jointing, filling the joints by neat cement slurry or approved colour grout, curing, finishing etc complete as directed by Engineer In Charge.	1701.00	Rupees One thousand seven hundred one only.	Sq.Mt.	4592.70
9	R2-CS-FL-32-a, Pg.73, (MCGM's Buildings Schedule/Common Schedule 2018)	29.79	Providing and fixing 8mm thk. ceramic tiles Light coloured glazed ceramic tiles conforming to I.S. 15622-2006 of approved quality, pattern and colour for dado in the wet area including preparing the surface and levelling in the desired line, backing of 20 thk. cement mortar in porportion 1:3 with approved waterproofing compound, square cut top edge or chamfered top edge in cement mortar 1:3, cement float, machine cutting, leveling, jointing, filling the joints with neat cement slurry or approved colour grout, finishing, curing etc complete as directed by Engineer In Charge.	1770.00	Rupees One thousand seven hundred seventy only.	Sq.Mt.	52728.30



Item. No.	Std. Specification	Quantity	Description	Rate		Unit	Amount
				In Figure	In words		
10	R2-CS-FL-01-c, Pg.61, (MCGM's Buildings Schedule/Common Schedule 2018)	22.35	Providing and laying polished natural stone 25 to 30 mm thk. Kota stone of size 0.430m x0.56m (17"x22") (Machine cut) of an approved quality and size for paving /flooring in plain and/or diamond /approved pattern including cement mortar bedding of 25 mm thick in 1:4 proportion, cement float, machine cutting, dressing, leveling, jointing, filling the joints with neat cement slurry or with required pigment, machine polishing at site, curing, finishing, etc complete as directed by Engineer In Charge.	1179.00	Rupees One thousand one hundred seventy nine only.	Sq.Mt.	26350.65
11	R2-CS-FL-28-d, Pg.71, (MCGM's Buildings Schedule/Common Schedule 2018)	2.51	Providing and fixing polished natural stone tiles 25 to 30mm thk. Kota stone of approved quality, pattern and colour for dado including preparing the surface and levelling in the desired line, backing of 20 thk. cement mortar in porportion 1:3, square cut top edge or chamfered top edge in cement mortar 1:3, cement float, machine cutting, leveling, jointing, filling the joints with neat cement or pigment mixed with cement, polishing, finishing, curing etc complete as directed by Engineer In Charge.	1559.00	Rupees One thousand five hundred fifty nine only.	Sq.Mt.	3913.09
12	Bd/V-5, P-551 (It.-2(a), Pg-124, PWD DSR 2015- 16 )	14.00	Providing and fixing G.I. Pipes 15 mm diameter heavy type having 21.3 mm outer diameter and 1.504 kilogramme per metre weight and having embossed at every metre as ISI mark and name of the manufacturer to walls, ceilings, floors etc. with screwed sockets, backnuts, elbows, tees, reducers, enlargers, plugs, clamps etc. including necessary drilling in holes in walls/slabs etc. and remaking good the demolished portion to restore the same in original condition neatly and applying primer and two coats of white oil painting including existing pipe, if necessary & conveying & stacking the same in P.W.D. chowky or as directed etc. complete.	313.00	Rupees Three hundred thirteen only.	R.Mt.	4382.00
13	(Bd/V-9, P-555, It.No.8(a), Pg.127) of PWD DSR 2015-16	3.00	Providing and fixing screw down 15 mm dia. Wheeled stop tap of gun metal bearing I.S.I. mark including sockets, union nut complete.	413.00	Rupees Four hundred thirteen only.	Nos.	1239.00
14	Bd/V-8 (It.5, Pg.126, PWD DSR 2015-16)	3.00	Providing & fixing heavy type 12 mm dia. Screw down bib/stop tap of brass including socket, union nut, etc. complete.	418.00	Rupees Four hundred eighteen only.	No.	1254.00



Item. No.	Std. Specification	Quantity	Description	Rate		Unit	Amount
				In Figure	In words		
15	Bd/V-30 (It.23(a), Pg.131, PWD DSR 2015-16)	2.00	Providing and fixing white glazed earthenware wash hand basin of 55 cm x 40 cm size including one cold water pillar tap, brackets, rubber plugs and brass chain, stop tap and necessary pipe connection including bottle trap and polyethylene waste water pipe upto the out side face of the wall, making good the damaged surface, testing etc. complete.	4345.00	Rupees Fopur thousand three hundred forty five only.	Each	8690.00
16	R2-CS-PN-3, Pg.56, (MCGM's Buildings Schedule/Common Schedule 2018)	62.91	Providing and applying first single coat of approved primer and two coats of acrylic distemper (oil bound distemper) of an approved make and colour as per manufacturers specifications to any surface, at all height and locations as directed including scaffolding, cleaning and preparing surfaces for painting with broom by any approved means, etc. complete as directed by Engineer-in-charge.	98.00	Rupees ninety eight only.	Sq.Mt.	6165.18
17	R2-CS-RM-34, Pg. 168, (MCGM's Buildings Schedule/Common Schedule 2018)	5.67	Removing white or colour wash by scrapping and sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete	11.00	Rupees Eleven only.	Sq.Mt.	62.37
18	R2-CS-PN-26, Pg. 193, (MCGM's Buildings Schedule/Common Schedule 2018)	9.27	Providing and applying synthetic enamel paint or flat oil paint in any requiered shade in 3 coats over a primer coat as per manufacturers specifications including scrapping, cleaning the surface etc. Complete.	200.00	Rupees Two hundred only.	Sq.mt.	1854.00
19	R2-CS-PS-155, Pg.155, (MCGM's Buildings Schedule/Common Schedule 2018)	4.00	Cutting holes up to 15x15 cm in R.C.C. floors and roofs for passing drain pipe etc. and repairing the hole after insertion of drain pipe etc. with cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size), including finishing complete so as to make it leak proof.	266.00	Rupees Two hundred sixty six only.	Each	1064.00



Item. No.	Std. Specification	Quantity	Description	Rate		Unit	Amount
				In Figure	In words		
20	Bd/E-2, P-288 (It.4, Pg.14, PWD DSR 15-16)	0.024	Providing and casting in situ cement concrete M-15 grade with minimum cement content 320 kg./cum as per approved make design as per BIS 456-2000 by Engineer-in-charge for bed blocks, foundations block and such other items including admixtures to accelerate, retard setting of concrete to improve workability without impairing strength and durability. The rates shall includes bailing out water manually centering, shuttering, compacting by vibrator and curing (Excluding reinforcement) etc. complete.	6882.00	Rupees Six thousand eight hundred eighty two only.	Cu.Mt.	165.17
21	(It. No. FMB 11.63 page B-54 of MCGM FMR)	0.05	Providing and fixing in position light weight M.S. Angies, tees, plates, rolled steel beams, joist and stanchions etc. including all labour and meterial in hoisting, fixing with bolts and nuts or by welding etc. complete including 3 coats of syn. Ena. paints (steel to be supplied by Municipal Corporation)	86568.00	Rupees Eighty six thousand five hundred sixty eight only.	M.T.	4328.40
22	It. No. 98, Page 113, PWD DSR 2015-16	1.80	Providing and fixing Seasoned Teak wood planking 25 mm thick for roof/ceiling as per existing details, tongue and grooved including scaffolding if necessary and one coat of primer complete. Item to include all mouldings and chamfers to be made as per original design indicated by the Architects. Item to include using a larger section of wood to get the mouldings and chamfers as per original design, sample to be got approved from the Architect before fixing.	2021.00	Rupees Two thousand twenty one only.	Sq.Mt.	3637.80
23	(It.-63, Pg-140, PWD DSR 2015-16)	500.00	Providing and fixing High Density Polyethylene UV stabilized water storage tank including conveying and hoisting in position confirming to I.S. 12701, with all leads and lifts of making necessary connection, testing and all required accessories including providing steel ladder as per M.C.G.M. requirement etc. complete. (Prior approval of sample by Executive Engineer is necessary before use).	7.00	Rupees seven only.	Ltr.	3500.00
24	(It.-43, Bd/v-18, P-558, Pg-137, PWD DSR 2015-16)	1.00	Providing and fixing 15 mm dia. Ball cock medium type with P.V.C. float including sockets and necessary fittings and tested as per municipal requirement etc.	243.00	Rupees Two hundred forty three only.	No.	243.00
25	R2-CS-DD-71, Pg. 187, (MCGM's Buildings Schedule/Common Schedule 2018)	6.00	Removing existing door or windows with frame and shutters and making good etc. to the existing surface.	563.00	Rupees Five hundred sixty three only.	Each	3378.00



Item. No.	Std. Specification	Quantity	Description	Rate		Unit	Amount
				In Figure	In words		
26	R2-CS-AW-04, Pg. 113, (MCGM's Buildings Schedule/Common Schedule 2018)	2.70	Providing and fixing in position aluminum louvered window with anodised aluminum frame of approved make and of size 40mm x 20mm x 2.0mm (wt. 0.605 kg/Rm) including adjustable aluminum frame, 4 to 6mm thk. frosted glass, fixtures and fastenings etc. complete as directed by by Engineer In Charge.	4246.00	Rupees Four thousand two hundred forty six only.	Sq.mt.	11464.20
27	It.No.103, Pg.115 of PWD DSR 2015-16	13.50	Providing and fixing prefabricated UPVC Door frame for door size 1.98 x 0.91 mtr. Along with all accessories like stainless steel screws, using 50 mm x 50 mm x 2.5 mm UPVC section. The UPVC frame section will be reinforced with G.I.C. channel. (excluding frame). Etc. complete.	441.00	Rupees Four hundred forty one only.	R.Mt.	5953.50
28	It.No.102, Pg.115 of PWD DSR 2015-16	3.89	Providing and fixing UPVC Door of size 1.98 m X 0.91 m or of read size and colour along with all accessories like Hinges, Tower Bolts, Aldrop, Screw, Handel, tadi, etc. hollow section of size 150 mm x 31 mm x 1.2 mm UPVC profile with bordar of "U" hollow size section of size 35mm x 35mm x 2mm the corner will be joined with tough plastic of "L" angles at all corners with stainless steel screws etc. complete.	3657.00	Rupees Three thousand six hundred fifty seven only.	Sq.Mt.	14225.73
29	(It.-35, Pg-65, PWD DSR 2015- 16)	10.47	Washing and cleaning any kind of tiled flooring, dado with washing powder and water.	13.85	Rupees Thirteen point eighty five only.	Sq.Mt.	145.01
30	R2-SE-8-6, Pg. 21, (MCGM's SE Schedule 2018)	1.00	Constructing brick masonry inspection chamber rectangular 0.9 M x 0.6M and 0.6M deep - do - including M20,30 cm thick capc.c.Bedding & including SFRC extra heavy duty frame and cover complete as per description initem No.SE-8-5etc. all complete as specified and directed.	19654.00	Rupees Nineteen thousand six hundred fifty four only.	No.	19654.00
31	R2-SE-8-6-a, Pg. 21, (MCGM's SE Schedule 2018)	0.50	Extra over above for every additional meter depth upto 2.5 M constructing brick masonry inspection chamber rectangular 0.9 M x 0.6M and 0.6M deep - do - including M20,30 cm thick capc.c.Bedding & including SFRC extra heavy duty frame and cover complete as per description initem No.SE-8-5etc. all complete as specified and directed.	16173.00	Rupees Sixteen thousand one hundred seventy three only.	m.depth	8086.50



Item. No.	Std. Specification	Quantity	Description	Rate		Unit	Amount
				In Figure	In words		
32	(It.16, Pg.39, PWD DSR 2015-16)	3.21	Removing any kind of debris including loading in truck and conveying to dumping point approved by BMC, unloading, spreading etc. complete. With all leads and lifts.	690.00	Rupees Six hundred ninety only.	Cu.Mt.	2214.90
33	(It.60(b), Pg.161, PWD DSR 2015-16)	8.00	Shooting of still photographs outdoor and indoor of construction and other works of building, bridges, roads, etc. in district and outside district at any distance. (Still Photo 4" x 6" size)	95.00	Rupees Ninety five only.	03 Copies each photo	760.00
						<b>Total Rs.</b>	<b>264,593.94</b>
						<b>Say Rs.</b>	<b>264,594.00</b>

**(Rupees Two lakhs sixty four thousand five hundred ninety four only)**

I/We hereby agree to quote \_\_\_\_\_% Above/Below or At par with the estimated cost put to the tender.

Therefore, the amount (in figure) \_\_\_\_\_ (in words) \_\_\_\_\_

Signature of Contractor/s

  
 Executive Engineer (City)/SPPL